

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 03/92

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 15-171-20,489-0000 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR McCoy Petroleum Corporation KCC LICENSE # 5003
(owner/company name) (operator's)
ADDRESS 3017 N. Cypress CITY Wichita,

STATE KS ZIP CODE 67226-4003 CONTACT PHONE # 816) 636-2737

LEASE Wasinger "B" WELL# 1-11 SEC. 11 T. 20S R. 33 (East West)

- E/2 - NE - SE SPOT LOCATION/QQQQ COUNTY Scott

1981 FEET (in exact footage) FROM S/2 (circle one) LINE OF SECTION (NOT Lease Line)

330 FEET (in exact footage) FROM E/2 (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET# _____

CONDUCTOR CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

SURFACE CASING SIZE 8-5/8" SET AT 355' CEMENTED WITH 250 SACKS

PRODUCTION CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: _____

ELEVATION 2945/2956 T.D. 4850 PBDT _____ ANHYDRITE DEPTH _____
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Plug and abandon using 60/40 Poz, 6%gel. Set 1st plug @ 2160' w/50 sx; 2nd plug set @ 1250' w/80 sx; 3rd plug set @ 390' w/50 sx; 4th plug set @ 40' w/10 sx; 15 sx in rathole and 10 sx in mousehole.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? _____ IS ACO-1 FILED? Yes

If not explain why? _____

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Daryl Hanson PHONE# 816) 272-1296

ADDRESS P. O. Box 2250 City/State Garden City, KS

PLUGGING CONTRACTOR Sweetman Drilling Inc. KCC LICENSE # 5658
(company name) (Contractor's)

ADDRESS 3017 N. Cypress PHONE # 816) 634-6151

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) _____

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 8-1-95 AUTHORIZED OPERATOR/AGENT: _____
(signature)

RECEIVED
STATE CORPORATION COMMISSION
8-7-95
AUG 17 1995
KCC LICENSE # 5658
(Contractor's)
CONSERVATION DIVISION
WICHITA, KANSAS