

15-051-00065-00-00
WELL PLUGGING RECORD


STATE OF KANSAS
 STATE CORPORATION COMMISSION

Give All Information Completely
 Make Required Affidavit
 Mail or Deliver Report to:
 Conservation Division
 State Corporation Commission
 800 Bitting Building
 Wichita, Kansas

OR
FORMATION PLUGGING RECORD

Strike out upper line
 when reporting plug-
 ging off formations.

Ellis County, Sec. 34 Twp. 14 Rge. 17 NE) W (W)
 Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SE SE NW **SUNWAW**
 Lease Owner John Lindas Oil, Inc.
 Lease Name Brull Well No. 1
 Office Address
 Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
 Date well completed 19...
 Application for plugging filed January 10 1952
 Application for plugging approved January 16 1952
 Plugging commenced January 10 1952
 Plugging completed January 13 1952
 Reason for abandonment of well or producing formation Dry



Locate well correctly on above
 Section Plat

If a producing well is abandoned, date of last production 19...
 Was permission obtained from the Conservation Division or its agents before plugging was com-
 menced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
 Producing formation Arbuckle Depth to top 3498' Bottom 5506' Total Depth of Well 3506' Feet
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	1025'	Cement from top to Bottom
				5-1/2"	3501'	2889'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from... feet to... feet for each plug set.

Filled hole back with crushed rock to 3490', dumped 4 sacks cement, top of cement 3460'. Mudded hole to 300' set rock bridge, dumped 20 sacks cement. Top of cement 235'. Mudded hole to 40', set rock bridge. Dumped 10 sacks of cement for cap.

JAN 21 1952
 01-21-1952

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to John Lindas Oil, Inc.
 Address 1316 Union National Bank Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
 I, B. L. Gilmer (employee of owner) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) B. L. Gilmer
 B. L. Gilmer Prod. Supt.
 (Address)

SUBSCRIBED AND SWORN to before me this 19th day of January, 1952

My commission expires October 8, 1955

Edward W. Wiem
 Notary Public.

22-2625 2-48-15M
 FILE 34-14-170
 BOOK PAGE 134 (line 27)

DRILLING LOG

TO: Prairie States Oil Company
 John D. McEwen
 Justin Riley
 Edward S. Siebert
 John Linds Oil, Inc

LEASE: Brull #1

County: Ellis
 Location: N $\frac{1}{2}$ NW $\frac{1}{4}$ S $\frac{1}{2}$ NW $\frac{1}{4}$
 Section: 34-14S-17W
 Elevation: 1960' DF 1963'RB

Rotary Total Depth: 3505'
 Commenced: 12-1-51; Completed 12-31-51
 Casing: 8 5/8" @ 1,045' with 500 sacks of cement and
 5 sacks of calcium chloride

Contractor: John Linds Oil, Inc. Rig #3
 1316 Union National Bank Building
 Wichita 2, Kansas

FIGURES INDICATE BOTTOM OF FORMATION

0	TO	60	Soil and Clay
60		70	Sand and Gravel
70		260	Blue Shale
260		570	Shale and Shells
570		695	Sand
695		975	Shale and Sand Streaks
975		1098	Red Bed
1098		1137	Anhydrite
1137		1450	Shale and Shells
1450		1560	Salt and Shale
1560		1800	Shale and Lime Streaks
1800		2110	Lime and Shale
2110		2180	Lime
2180		2260	Lime and Shale
2260		2965	Lime and Shale
2965		3490	Lime
3490		3498	Conglomerate
3498		3505	Arbuskle TD

STATE OF KANSAS)
) ss
 COUNTY OF SEDGWICK)

I, the undersigned, being duly sworn on oath,
 state that the above statement and log is a true
 and correct record of the well drilled by John
 Linds Oil, Inc. at the location above described.

Edward W. Wiens

Subscribed and sworn to before me, this 31st day of
 December, 1951.

Caroline J. Carney

My Commission expires March 25, 1952.

PLUGGING
 FILE SEC-31-14-17W
 BOOK PAGE 134 LINE 22

JAN 17 1952
 CO-01-17-1952