

15-051-20115-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Ellis County, Sec. 34 Twp. 14S Rge. (E) 17 (W)

Location as "NE/CNW&SW" or footage from lines NE NW NW

Lease Owner Aspen Drilling Co.

Lease Name Brull Well No. 1

Office Address P. O. Box 783, Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) dry hole

Date well completed September 26 19 67

Application for plugging filed November 1 19 67

Application for plugging approved October 2 19 67


Plugging commenced September 27 19 67

Plugging completed same 19

Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Leo Massey

Producing formation Depth to top Bottom Total Depth of Well Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Table with 7 columns: FORMATION, CONTENT, FROM, TO, SIZE, PUT IN, PULLED OUT. The table is currently empty.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Hole plugged with pump truck. 100 sacks 50/50 Pozmix with 4% gel.

NOV 2 1967
11-02
1967

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Aspen Drilling Co.

Address P. O. Box 783, Great Bend, Kansas

STATE OF Kansas COUNTY OF Barton, ss.

William S. Schachle (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well is filed and that the same are true and correct. So help me God.

(Signature) William S. Schachle

P. O. Box 783, Great Bend, Kansas

(Address)

Sworn to before me this 1st day of November, 1967

My commission expires April 18, 1968



Theora Holloman
Notary Public.

15-051-20115-00-00

D R I L L E R S L O G

NOV 2 1967
11-02-1967

COMPANY: Aspen Drilling Co.
 CONTRACTOR: Aspen Drilling Co.
 LEASE NAME: Brull #1
 LOCATION: NE NW NW Sec.34-T14S-R17W
 Ellis County, Kansas
 ELEVATION: 1966 KB
 SURFACE CASING: 249' 8 5/8" casing
 COMMENCED: September 16, 1967
 COMPLETED: September 26, 1967
 ROTARY TOTAL DEPTH: 3602'

<u>FORMATION</u>	<u>DEPTH</u>	
		Drilled 12 1/4" hole to 249'. Ran 249' 8 5/8" casing, cemented with 165 sacks cement.
Clay-Sand	60	
Shale	251	
Red Bed	370	DST #1 3214 - 3260
Sand	585	DST #2 3288 - 3305
Dakota Sand	750	DST #3 3347 - 3390
Anhydrite	1141	DST #4 3390 - 3410
Red Bed	1695	DST #5 3527 - 3602
Lime-Shale	2150	DST #6 3422 - 3440
Lime	2285	
Shale	2740	Ran electric log. D & A
Shale-Lime	2920	
Lime	3575	
Arbuckle	3602	

LOG TOPS

Anhydrite	1102
Heebner	3179
Toronto	3199
Lansing	3228
Base KC	3452
Conglomerate	3485
Arbuckle	3520
RTD	3602

STATE OF KANSAS)
) ss:
 COUNTY OF BARTON)

The undersigned, being duly sworn on oath, states that the above statement and log are a true and correct record and log of the well drilled at the location above described.

William S. Schachle
 William S. Schachle

Subscribed and sworn to before me this 1st day of November, 1967.

Theora Holleman
 Theora Holleman, Notary Public

Commission expires: April 18, 1968.

