


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

Ellis County, Sec. 27 Twp. 14S Rge. (E) 17 (W)

Location as "NE/CNW/SW" or footage from lines NW NW SW
Lease Owner Murfin Drilling Company
Lease Name Herl Well No. 1
Office Address 617 Union Center, Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed April 30 1959
Application for plugging filed April 30 1959
Application for plugging approved April 30 1959
Plugging commenced April 30 1959
Plugging completed April 30 1959
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well _____
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3540 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	178'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled with mud and sand to 450'.
Set 1st plug at 450'. Pumped in 40
sxs cement. Filled hole with mud
to 150'. Set 2nd plug at 150'. Pumped
in 20 sxs. cement. Filled hole with mud
to 40'. Mixed and displaced 10 sxs.
cement through drill pipe.

RECEIVED
STATE CORPORATION COMMISSION
MAY 19 1959
7 5 / 19
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Murfin Drilling Company
Address 617 Union Center, Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
W. R. Murfin (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W R Murfin
617 Union Center, Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 12th day of May, 1959

My commission expires March 23, 1960
Donna M. Matzek Notary Public.

PLUGGING
FILE SEC 27 T. 14 R. 17W
BOOK PAGE 30 LINE 9

15-051-04136-00-00
WELL LOG

COMPANY **Murfin Drilling Company**

SEC. 27 T. 14S. 17W

FARM **Herl**

NO. **1**


LOC. **NW NW SW**

TOTAL DEPTH **3540'**

COUNTY **Ellis**
KANSAS

COMM. **4-22-59**

COMP. **4-30-59**



SHOT OR TREATED

CONTRACTOR **Murfin Drilling Company**

ISSUED

CASING

20 10
15 8 5/8" @ 178' w/135 sxs.
12 6
13 5

ELEVATION **1964' K. B.**

1959' G. L.

PRODUCTION **D & A**

FIGURES INDICATE BOTTOM OF FORMATIONS

178	Surface Hole	TOPS:	
330	Shale - Shells	Topeka	2910
570	Shale - Sand	Heebner	3181
755	Sand	Toronto	3200
1104	Red Bed	Lansing-Kansas City	3228
1146	Anhydrite	Base Kansas City	3458
1520	Shale - Shells	Conglomerate	3479
1730	Salt - Shale	Arbuckle	3512
1870	Shale - Lime Shells		
3220	Lime - Shale		
3515	Lime		
3540	Arbuckle		

DST #1 3290-3316

Open 2 hrs. Rec. 245' muddy salt water. IF 0#. FF 85#. BHP 720# in 20 minutes.

DST #2 3393-3410

Open 1 hr. Rec. 10' mud. IF 0#. FF 0#. BHP 0#/ 20 min.

CONSERVATION DIVISION
 Wichita, Kansas
 MAY 19 1959
 05-19-1959

PLUGGING
 FILE SEC 27 T. 14 S. R. 24
 BOOK PAGE 48 LINE 980

State of Kansas }
 County of Sedgwick } ss:

I, W. R. Murfin of the Murfin Drilling Company

upon oath state that the above and foregoing is a true and correct copy of the log of the Herl #1 well.

W. R. Murfin

Subscribed and sworn to before me this 12th day of May 19 59

My Commission Expires: March 23, 1960

Donna M. Matzek
Donna M. Matzek LIC