

15-051-01030-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

OR

FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging off formations.

Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines Ellis County. Sec 27 Twp 14 Rge. (E) 17(W)
Ctr. SW/4 NW/4 SW/4


Lease Owner Lion Oil Company
Lease Name Catherine Well No. 1
Office Address P. O. Box 639, Pratt, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Oil Well
Date well completed 1-19 1952
Application for plugging filed 3-20 1953
Application for plugging approved 3-20 1953
Plugging commenced 3-20 1953
Plugging completed 3-20 1953

Reason for abandonment of well or producing formation Well had ceased to produce enough oil to be marketable.

If a producing well is abandoned, date of last production November 19 1952

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation..... Depth to top..... Bottom..... Total Depth of Well 3505 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	233'	0
				5-1/2"	3491'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from.....feet to.....feet for each plug set.

Plugged back from 3505' to 325' with 20 sacks of heavy mud. Plugged back from 325' to 5' with 1 cement plug and 40 sacks of cement. Cement pumped in under 2000# pressure.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Vernon Hayes
Address P. O. Box 639
Pratt, Kansas

STATE OF KANSAS, COUNTY OF PRATT, ss.

Vernon Hayes (employee of owner) ~~representative~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Vernon Hayes

P. O. Box 639, Pratt, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 28th day of March, 1953

My commission expires August 29, 1955

Dan Dwick
Notary Public.

PLUGGING
FILE SEC 27T 14 R 17W
BOOK PAGE 56 LINE 20

MAR 30 1953
03-30-1953
CONSERVATION DIVISION
Wichita, Kansas

15-051-01030-00-00

CATHERINE #1

SW $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ 27-14S-17W

Ellis County, Kansas

Rigging up Rotary Tools 12/21/51
Tearing down Rotary Tools 1/10/52

Run 11 Jts. 5 5/8" 24' 8 Rd. Thd.
Surface pipe set @ 233' with 150 sks
Run 93 Jts. 5 1/2" extreme casing set
@ 3497' with 150 sks. Pumped 600 sks
cement around top of pipe.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>
Sand & Shale	0'	215'
Shale & Shells	215	240
Shale	240	560
Sand	560	580
Shale	580	960
Sand & Shale & Shells	960	1100
Shale & Shells	1100	1130
Anhydrite	1130	1160
Shale & Red Beds	1160	1232
Shale & Shells	1232	1515
Shale & Shell & Lime Streaks	1515	1780
Shale & Lime	1780	1915
Shale & Shells & Lime Streaks	1915	2060
Lime	2060	2243
Broken Lime	2243	2375
Shale & Lime	2375	2517
Broken Lime	2517	2640
Broken Shale & lime	2640	2705
Broken Lime	2705	3030
Lime	3030	3070
Broken Lime	3070	3172
Shale & Lime	3172	3255
Lime	3255	3330
Broken Lime	3300	3335
Lime & Shale	3335	3358
Lime	3358	3388
Lime & Shale	3388	3410
Lime	3410	3460
Lime & Shale	3460	3493
Conglomerate & Lime	3493	3500 Total Depth

I, Don S. Packer, do hereby certify that the foregoing log is true and correct, to the best of my knowledge and belief.

Don S. Packer

Subscribed and sworn to before me this 26th day of March, 1953.

Warren J. Kopke

My commission expires: September 24, 1955.

PLUGGING
 FILE SEC 27 14 17W
 BOOK PAGE 86 LINE 20

RECEIVED
 STATE CORPORATION COMMISSION
 MAR 30 1953
 03-30-1953
 CONSERVATION DIVISION
 Wichita, Kansas