


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

WELL PLUGGING RECORD

15-051-06805-00-00

NORTH



Locate well correctly on above
Section Plat

Ellis County, Sec. 27 Twp. 14S Rge. (E) 17 (W)
Location as "NE/CNW/SW" or footage from lines C - NW/4 SW/4 SW/4
Lease Owner Lion Oil Company
Lease Name Jerome Well No. 1
Office Address P. O. Box 639, Pratt, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil Well
Date well completed 3-19 19 52
Application for plugging filed 4-14 19 54
Application for plugging approved 4-15 19 54
Plugging commenced 4-30 19 54
Plugging completed 4-30 19 54
Reason for abandonment of well or producing formation Well had ceased to produce.
If a producing well is abandoned, date of last production 12-22 19 53
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Eldon Petty
Producing formation Arbuckle Depth to top 3485 Bottom 3498 Total Depth of Well 3498 Feet
Show depth and thickness of all water, oil and gas formations. Plugged Back T. D. 3415 feet

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|-------|--------|------------|
| | | | | 8-5/8 | 207 | 0 |
| | | | | 5-1/2 | 3478 | 0 |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged back from 3415 feet to 320 feet with 35 sacks of jel. Plugged back from 320 feet to 8 feet with 1 cement plug and 40 sacks of cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Halliburton Oil Well Cementing Company
Address Hays, Kansas

STATE OF KANSAS COUNTY OF PRATT, ss.
Vernon Hayes (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Vernon Hayes
P. O. Box 639, Pratt, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 1st day of May, 19 54

My commission expires August 29, 1955

Dan Deibel
Notary Public.

PLUGGING
FILE REC 22 T 14 R 17W
BOOK PAGE 22 LINE 9

MAY 3 - 1954
05-03-1954
CONSERVATION DIVISION
Wichita, Kansas

WELL LOG JEROME NO. 1

Lion Oil Company, Lease Owner

Section 27, Twp. 14S, Rge. 17W

Garvey Drilling Company, Contractor

Location: NW SW SW

Drilling Commenced: January 9, 1952

County: Ellis, Kansas

Drilling Completed: January 14, 1952

R.T.D.: 3488'

Casing Record: 8 5/8" @ 209' w/125 sex
5 1/2" @ 3485' w/150 sex

Figures below indicate bottom of formations:

| | | |
|-------|-----------------|----------------|
| 55 | Shale & Sand | |
| 570 | Shale | |
| 680 | Sand | |
| 725 | Shale & Shells | Anhydrite 1095 |
| 1000 | Shale & Red Bed | |
| 1095 | Red Bed | |
| 1140 | Anhydrite | |
| 1490 | Shale & Shells | |
| 1815 | Salt & Shale | |
| 1975 | Lime & Shale | |
| 2070 | Lime | |
| 2245 | Lime & Shale | |
| 2340 | Lime | |
| 3045 | Lime & Shale | |
| 3488 | Lime | |
| 3488' | R.T.D. | |

I hereby certify that this is a true and correct log of the above mentioned well.

GARVEY DRILLING COMPANY

By Eric F. J...

STATE OF KANSAS)
) SS;
COUNTY OF SEDGWICK)

Subscribed to and sworn to before me, a Notary Public, in said County and State, this 21st day of January, 1952.

Charlotta Heidman
Notary Public

My commission expires October 13, 1954

RECORDED
STATE OF KANSAS

COPIED 04-15-1954

PLUGGING
FILE SEC 22 T 14 R 17 W
BOOK PAGE 27 LINE 2