

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-053-19127 00-00

LEASE NAME Frank G. Hlaus

WELL NUMBER 1-16

SPOT LOCATION C W/2 SE SE NE

SEC. 16 TWP. 14 RGE. 10W (E) or (W)

COUNTY Ellsworth

Date Well Completed _____

Plugging Commenced 4-24-86

Plugging Completed 5-12-86

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Kelso Casing Pulling Bought F/Davies & Company
Inc.

ADDRESS Box 347 Chase, Kansas 67524

PHONE # (316) 938-2457 OPERATORS LICENSE NO. 6050

Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Salina, Kansas

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom T.D. 2310'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	410'	none
				4-1/2"	2309'	1591'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from _____ feet to _____ feet each set.

Plugged off bottom with sand to 2080' and 4 sacks cement. Shot pipe @1697', 1591', pulled 40 joints of 4-1/2" casing. Plugged surface with 3 hulls and 100 sacks econolite w/2 hulls.
Plugging Complete

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050
Address P.O. Box 347 Chase, Kansas 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347 Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 14 day of May, 19 86

Irene Hoover
Notary Public

My Commission expires: _____



RECEIVED
STATE CORPORATION COMMISSION
MAY 16 1986
05-16-86
CONSERVATION DIVISION
Wichita Kansas

15-053-19127-00-00

PROPERTY MANAGEMENT
LEASE OPERATIONS

A SERVICE OF THE OIL INDUSTRY

WELL COMPLETIONS
RE-COMPLETIONS

LEITH OPERATIONS, INC.

427 UNION CENTER BLDG.
WICHITA, KANSAS 67202
TELEPHONE 316-265-3491

*8 1/2 cft/cu
Cement used*

DAVIES & COMPANY, INC.
4501 E. 31st. Street-Suite 101
Tulsa, Oklahoma 74135

FRANK G. HLAUS NO. 1-16
C W/2 se se ne 10-14S-10W
Ellsworth County, Kansas

CASING RECORD

August 24, 1980

Ran, set and cemented 58 jts. 4 1/2" OD 9.5# 8rd. R-3, Casing @ 2309'
(1' off total depth) Cemented w/ 150 sacks common cement - 10% salt
Finish @ 3:35 AM 8-24-80.

Shoe joint 40.27' long - Float @ 2268'

Centralizers- 2268', 2148', 2108' and 1987'.

Good returns at surface during cementing.

Note: 4 jts. csg. + cut off extra and left on location.

DIRECTIONS: Wilson (between old 40&I-70) 2 miles East - 1/2 mi. North -
West to location.

Supervised by:

LeeRoy Cline

Tulsa, Oklahoma 74135

Ellsworth County, Kansas

COMPLETION RECORD

SUMMARY:

PBTD 2242'
Perforations: 2161-64' & 2138-43'
Stimulation: 65000# sand - Fracture.
Tubing: 69 jts. 2119' - 2-3/8" OD EUE 8rd.
Seating Nipple: 2-3/8" x 12"
Mud Anchor: 2-3/8" x 30' w/ 3' perf.

RECEIVED
STATE CORPORATION COMMISSION

MAR 3 1986

CONSERVATION DIVISION
Wichita, Kansas