


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Ellsworth County, Sec. 5 Twp. 14S Rge. 10W (W)
Location as "NE/CNW/SW" or footage from line Approx SE NE SE
Lease Owner Leon F. Dolecek
Lease Name KUCK Well No. 1
Office Address Wilson, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed April 20 1967
Application for plugging filed April 20 1967
Application for plugging approved April 20 1967
Plugging commenced April 20 1967
Plugging completed April 20 1967
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3491 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
<u>Shale & Shells</u>		<u>0</u>	<u>296</u>	<u>8 5/8"</u>	<u>296'</u>	<u>NONE</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with mud 285', 1/4 sacks hulls wooden plug
25 sacks cement.

Filled hole with mud 40', 1/4 sack hulls wooden plug
10 sacks cement.

Two sacks in Rat Hole.

APR 25 1967
CONSULTING ENGINEER
Wichita, Kansas
04-24-67

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Isern Drilling Company
Address BOX 486, ELLINWOOD, KANSAS 67526

STATE OF KANSAS, COUNTY OF BARTON, ss.
W. F. Banks (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. F. Banks
Box 486, Ellinwood, Kansas 67526
(Address)

SUBSCRIBED AND SWORN TO before me this 20th day of April 1967
George A. Meyer Notary Public

My commission expires February 10, 1971.

W E L L L O GRECEIVED
STATE CORPORATION COMMISSION

APR 25 1967

Leon F. Dolacek's KUCK #1
 Approx. SE NE SE
 Section 5-14S-10W
 Ellsworth County, Kansas

CONSERVATION DIVISION
 Wichita, Kansas

ELEVATION: 1743' GL; 1745' DF; 1747' KB.

Figures indicate bottom of formation:

PIPE RECORD:

8 5/8" set at 293'
 cemented with 170 sacks.

ROTARY COMMENCED: 4-10-67

ROTARY COMPLETED: 4-20-67


0	to	10	cellar
		296	shale & shells
		417	shale
		421	pyrite
		450	shale
		567	red bed
		695	shale
		1420	shale & shells
		1920	lime & shale
		2210	shale shells
		2234	shale
		2365	lime & shale
		2450	shale & shells
		3491	lime & shale
		3491	Rotary Total Depth

STATE OF KANSAS)
) ss
 COUNTY OF BARTON)

I, Dean Wells, Partner of Isern Drilling Company, contractor for the above-described well, being first duly sworn on oath, declare: That I have knowledge of the facts statements and matter herein contained pertaining to the log of the above-described well, as filed, and that the same are true and correct.


 Dean Wells - Partner

Subscribed and sworn to before me on this 24 day of April, 1967.


 George A. Meyer, Notary Public

My commission expires: February 10, 1971.