


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Ellsworth County, Sec. 4 Twp. 14S Rge. 10W (~~E~~) (~~W~~)
Location as "NE/CNW/SW" or footage from lines C SW/4
Lease Owner ISERN-WELLS
Lease Name BARTUNEK Well No. 1
Office Address BOX 486, Ellinwood, Kansas 67526
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed November 17 1966
Application for plugging filed November 17 1966
Application for plugging approved November 17 1966
Plugging commenced November 17 1966
Plugging completed November 17 1966
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman, Holyrood, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3435 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
<u>Shale & Shells</u>		<u>215</u>	<u>285</u>	<u>8 5/8</u>	<u>285'</u>	<u>NONE</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

plug
Used 1/4 sack hulls and 25 sacks cement at 280'.

and filled with heavy mud 280' to 40'.

plug
Used 1 1/2 sacks hulls and 10 sacks cement at 40'.

Used 2 sacks cement in rat hole.

Handwritten notes and stamps:
NOV 20 1966
11-22-66

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor ISERN DRILLING COMPANY
Address BOX 486, ELLINWOOD, KANSAS 67526

STATE OF KANSAS, COUNTY OF BARTON, ss.
W. F. Banks (employee of owner) or (~~OWNER REPRESENTATIVE~~) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. F. Banks
Box 486, Ellinwood, Kansas 67526
(Address)

SUBSCRIBED AND SWORN TO before me this 19th day of November, 1966

George A. Meyer
George A. Meyer Notary Public.

My commission expires February 10, 1967.

W E L L L O G

ISERN-WELLS, et al BARTUNEK #1
 C SW/4, Section 4-14S-10W
 Ellsworth County, Kansas

Figures indicate bottom of formation:

ELEVATION: 1730' KB

PIPE RECORD:

8 5/8" set at 285'
 with 170 sackcement.

ROTARY COMMENCED: 11-9 -66
 ROTARY COMPLETED: 11-17-66

LOG TOPS:

Topeka	2468
Heebner	2760
Brown Lime	2859
Lansing	2882
Conglomerate Sand	3248
Viola	3328
Simpson Shale	3388
Simpson Sand	3406
Arbuckle	3430
Log Total Depth	3437

0	to	10	cellar
		100	lime & shale
		285	shale & shells
		375	shale, iron & pyrite
		405	sand
		420	shale
		527	red bed
		1185	shale
		1270	shale & shells
		1486	shale & lime
		1835	lime & shale
		2470	shale & shells
		2806	lime & shale
		2844	shale & lime
		3435	lime & shale
		3435	Rotary Total Depth

RECORDED
 NOV 22 1966
 EXAMINATION DIVISION
 STATE OF KANSAS

STATE OF KANSAS)
 COUNTY OF BARTON) ss

I, Dean Wells, Partner of Isern Drilling Company, contractor for the above-described well, being first duly sworn on oath, declare: That I have knowledge of the facts, statements and matter herein contained pertaining to the log of the above-described well, as filed, and that the same are true and correct.

Dean Wells
 Dean Wells, Partner

Subscribed and sworn to before me on this 21st day of November, 1966.

George A. Meyer
 George A. Meyer, Notary Public

My commission expires Feb. 10, 1967.