


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Ellsworth County, Sec. 4 Twp. 11 Rge. 10 (E) (W) X
C SW



Locate well correctly on above Section Plat

Location as "NE/CNW/SW" or footage from lines.
Lease Owner American Drilling Company, Ltd.
Lease Name Bartunek Well No. 1 (OWO)
Office Address 360 Sutton Place Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed 12-11-70 19____
Application for plugging approved 12-12-70 19____
Plugging commenced 12-31-70 19____
Plugging completed 1-2-71 19____
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 2660 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	285	None
				4 1/2	2286	1823' .16

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Killed gas. Pushed a plug down to 2100'; dumped 30 gallons of sand and 4 sacks of cement. Worked 10" tension at 1600 psi. Shot casing at 1818' and laid down 58 joints. Set a plug at 285' and 10' rock bridge. Dumped 35 sacks of cement, mudded hole to 35' and dumped 10 sacks on top.

RECEIVED
STATE CORPORATION COMMISSION
JAN 14 1971
CONSERVATION DIVISION
Wichita, Kansas


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Forbes Casing Pulling Company, Inc.
Address P. O. Box 221 Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Barton, ss.
James W. Rockhold (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James W. Rockhold
P. O. Box 221 Great Bend, Kansas
(Address)

Subscribed and sworn to before me this 12 day of January, 19 71



Alice Hichel
Notary Public.

My commission expires May 27, 1973

15-053-30159-00-01

RECEIVED
STATE CORPORATION COMMISSION
DEC 14 1970
CONSERVATION DIVISION
Wichita, Kansas

DRILLERS LOG

COMPANY American Drilling Company
 CONTRACTOR: American Drilling Company
 FARM. Bartunek No. 1 (OWWO)
 LOCATION: C SW, Section 4-14S-10W
 Ellsworth County, Kansas
 COMMENCED: December 5, 1968
 COMPLETED: December 14, 1968

<u>FORMATION</u>	<u>DEPTH</u>	Elevation: 1730' K.B.
Drill cement & plug	0 to 285'	Surface casing (8-5/8") in old hole was set at 285'.
Washdown	285 to 520'	
Reaming & washdown	520 to 890'	Washed down and cleaned out old hole to 1372'. New hole from 1372' to 2660' RTD. DST #1: 2100-2185' DST #2: 2503-2530' Ran 22 Jts. 4-1/2" casing. Set at 2286', cemented with 75 sx. 50/50 Pozmix salt saturated cement, 2% gel. Pumped plug to 2254' with 37½ B.W.
Washdown	890 to 1318'	
Milling	1318 to 1370'	
Lime	1370 to 1500'	
Ft. Riley	1500 to 1670'	
Lime & Shale	1670 to 1995'	
Lime	1995 to 2160'	
Lime & Shale	2160 to 2185'	
Lime	2185 to 2235'	
Lime & Shale	2235 to 2490'	
Lime	2490 to 2660'	
RTD	2660'	

<u>SAMPLE TOPS</u>	<u>DEPTH</u>
Foraker	1919 (-189)
Indian Cave	2095 (-365)
Grand Haven	2139 (-409)
Tarkio Lime	2217 (-487)
Willard Shale	2244 (-514)
Elmont	2288 (-558)
Howard	2434 (-704)
Topeka	2513 (-783)
RTD	2660 (-930)

A F F I D A V I T

STATE OF KANSAS)
)
 COUNTY OF SEDGWICK) ss:

I, Larry G. Stephenson, of the American Drilling Company, do hereby certify and state: That I have knowledge of the facts, statements and matters herein contained and that the same are true and correct.


 Larry G. Stephenson

DEC 8 1970