

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

OR
FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging off formations.

Ellsworth County, Sec. 36 Twp. 14 Rge. 10 (E) (W)

Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NW SW SW

Lease Owner Albert Borell et al

Lease Name Ernest Mattas Well No. #1

Office Address Russell, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed May 19 19 50

Application for plugging filed May 20 19 50

Application for plugging approved May 20 19 50


Plugging commenced May 20 19 50

Plugging completed May 21 19 50

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes



Locate well correctly on above
Section Plat

Name of Conservation Agent who supervised plugging of this well Ruel Durkee, McPherson, Kansas

Producing formation Depth to top Bottom Total Depth of Well Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				10"	209'	None
				Cemented	Top To Bottom	
				7"	2790'	1291'
				Cemented	W/50 Sacks Cement	
				5 1/2"	2944'	2944'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Hole filled with rotary mud to 2725'
Plug and bridge set at 2725'
5 sacks cement placed on top of bridge at 2725'
Mud to 200'
Plug and rock bridge set at 200'
20 sacks cement placed on top of bridge at 200'
Mud to 35'
Plug and rock bridge set at 35'
10 sacks cement on top of plug at 35' to top of hole

05-25-50

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to O. G. Stearns

Address Russell, Kansas

STATE OF Kansas, COUNTY OF Russell, ss.

O. G. Stearns (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-
described well as filed and that the same are true and correct. So help me God.


(Signature) *O. G. Stearns*

Russell, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 22nd day of May, 19 50

Harold J. Urbonek
Notary Public.

My commission expires June 20, 1953



MATTAS # 1

Company: Stearns Petroleum, Inc.,
 Commencement date: 4-2-50
 Completion date: 5-19-50

Location: NW SW SW, Sec. 36, T14, R10,
 Russell County, Kansas

Elevation: 1621' D. F.

Casing record:

10-3/4" 209'
 cmtd. w/110 sxs.
 7" 2790'
 cmtd. w/50 sxs.
 5" 2944'

Totco:

0° 155'
 1° 715'
 1-1/2° 1295'
 1° 1370'
 3/4° 1507'
 3/4° 1725'
 3/4° 1960'
 1° 2711'

WELL LOG

surface	0	65
shale and shells	65	209
blue shale and iron	209	350
red rock	350	382
Anhydrite	382	418
shale and shells	418	465
red rock	465	550
shale and shells	550	850
salt	850	1005
shale and shells	1005	1355
shale and lime	1355	2700
lime	2700	2790
R. T. D.	2790	
lime	2790	2818
broken lime	2818	2823
lime	2823	2840
shale	2840	2843
lime	2843	2847
shale	2847	2853
lime	2853	2929
shale	2929	2933
lime	2933	2995
shale	2995	2997
lime	2997	3050
Conglomerate	3050	3100
lime	3100	3137
Total Depth	3137	

STATE OF KANSAS)
) SS
 COUNTY OF RUSSELL)

I hereby certify that the above information is true and correct to the best of my knowledge.

[Signature]

Subscribed and sworn to before me this 22nd day of May, 1950.

[Signature]
 NOTARY PUBLIC

My commission expires: June 20, 1953

