


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Ellsworth County, Sec. 35 Twp. 14 Rge. 10 E/W
Location as "NE/CNW $\frac{1}{2}$ /SW $\frac{1}{2}$ " or footage from lines
S/2 N/2 NW

Lease Owner Albert Borrell Oil Co.
Lease Name Vanek #2 Well No. _____
Office Address Wilson, Kansas
Character of Well (Completed as Oil, Gas or Dry Hole) _____



Date Well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 7/28/77 _____ 19____
Plugging completed 8/15/77 _____ 19____
Reason for abandonment of well or producing formation
depleted.
If a producing well is abandoned, date of last production _____ 19____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Toman
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 2908'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	230	none
				5 1/8"	2905	2488'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sanded to 2875' and ran 5 sacks cement. Loaded hole with salt water. Shot pipe at 2496', pulled 62 joints. Pumped 3 sacks hulls, 20 sacks gel and 85 sacks cement.

PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KELSO CASING PULLING
CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.

R. DARRELL KELSO (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
CHASE, KANSAS

(Address)

SUBSCRIBED AND SWORN TO before me this 16th day of August, 19 77

My commission expires _____



Margaret Melcher
Notary Public.

KANSAS DRILLERS LOG

Walt 1-7-75

API No. 15 — Ellsworth — 20387-00-00
 County Number

S. 35 T. 14 R. 20^E
 Loc. 8 1/2 n 1/2 nw


Operator
Borrell Oil Co. (Albert H. Borrell)

County Ellsworth

Address
Hilson, Kansas 67100

640 Acres
 N

Well No. 2 Lease Name
Charles Vanek



Footage Location
 foot from (N) (S) line foot from (E) (W) line

Principal Contractor Hilson Exploration and Development, Inc. Geologist Richard M. Foley

Start Date drill start completed 10/22/78 Well Depth 2908 P.B.T.D.

Elev.: Cr. 1672
 DF 1672 KD

Date Completed 11/7/76 Oil Purchaser

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing col (in O.D.)	Weight (lb./ft.)	Setting depth	Type cement	Sacks	Type and percent additives
		<u>8 5/8</u>		<u>230</u>	<u>CO</u>	<u>120</u>	
		<u>5 1/2</u>		<u>2905</u>	<u>"</u>	<u>75</u>	
	<u>survey</u>	<u>1320 FWL</u>	<u>990 Fnl</u>				
		<u>Anhy 406-83 (01216)</u>					

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Factor set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	STATE COMMISSION ON CONSERVATION	Depth interval treated
	<u>JUL 15 1977</u>	
	<u>CONSERVATION DIVISION</u>	
	<u>Wichita, Kansas</u>	

INITIAL PRODUCTION

Date of first production: <u>11/7/76</u>	Producing method (flowing, pumping, gas lift, etc.):
DATE OF PRODUCTION PER 24 HOURS	Oil <u> </u> Gas <u> </u> Water <u> </u> Gas-oil ratio <u> </u>
Disposition of gas (vented, used as lift gas or sold)	bbls. MCF bbls. CFPB
Producing interval(s)	

INSTRUCTIONS: As provided by ICC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Menard Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Main (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator **Borell Oil Co. (Albert W. Borell)** DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWD, ETC.:
 Well No. **2** Log Name **Charles Vanok** 011

S 35 T 14 R 10^E

WELL LOG

Show all important zones of porosity and contents thereof; corad intervals, and all drill-stem tests, including depth interval tested, surface used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Sappa & Grd ls formation				46
Dakota form				185
Kiowa Form				273
Harper silt				478
stone corral (anhydrite tp)				498
Hutchinson sl tp				866
" baso				1171
Chase lm gr tp				1171
Ft. Riley lm tp				1386
Neva lm tp				1734
Foraker lm tp				1849
Grandhaven				2033-361
Tarkio				2109-437
Elmont				2171-499
Howard				2320-648
Topska				2354-682
Wilson Crk -Topeka				2397-725
King Hill				2489-817
Queen Hill				2562-890
Heelner				2647-975
Toronto				2865-993
Douglas				2678-1006
Brown Lm				2744-1072
Lansing				2766-1072 1094
Dist #1 2379-2409 Opern 40 min (20-20-20-20) slide 30' Recover 200' mud tool plugged				
Dist #2 2785-2808 oporn 1 hr (30-30-30-30) slide 6' recover 60' gas 90' gassy md. 30" sip-691 - 837 pr Fp 48-48 58-58 temp 100				
				Dist #3 2854-2867 Op 2 hrs (30-30-90-30) slide 10 to bottom Recover, 240' gas 125' gassy oil cut mud 30" sip-1031; 968# Fp-58-58 58-68# Temp 100

RECEIVED
 STATE GEOLOGICAL COMMISSION
 JUL 15 1977
 CONSERVATION DIVISION
 Wichita, Kansas

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received _____

Signature **Julius Ehrlich**
 Title **Pres.**
 Date **January 7, 1975**