

STATE OF KANSAS
STATE CORPORATION COMMISSION

File All Information Completely
State Required Affidavit
Must be Delivered Report to
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217

WELL PLUGGING RECORD

Ellsworth County, Sec. 34 Twp. 14 Rge. 10 (E) W (W)
Location as "NE/CNWESW" or footage from lines NE NE NW
Lease Owner Albert Borrell
Lease Name Macek Well No. #1
Office Address Box 391, Wilson, Ks. 67490
Character of Well (completed as Oil, Gas or Dry Hole) Completed as an oil well
Date well completed July, 1972 19
Application for plugging filed May 1974
Application for plugging approved May 1974
Plugging commenced May 16 1974
Plugging completed June 20 1974
Reason for abandonment of well or producing formation Insufficient oil production

	X		

Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production April, 1974 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman
Producing formation Kansas City Depth to top 2781 Bottom 2884 Total Depth of Well 2886 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	226	None
				5 1/2"	2882	2297

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

May 16, 1974 Plugged off bottom. Dumped sand to 2850'. Mixed and dumped 5 sx of cement.
June 20, 1974 Plugged off top. Allied Cementing Co. mixed and pumped down 8 5/8" surface casing, 2 sx of hulls, 20 sx of gel and 85 sx of cement.

RECEIVED
AUG 9 1974
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
Wichita, Kansas


(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor RUSS CASING PULLING, INC.
Address P. O. Box 1082, Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Ellsworth ss.
Albert W. Borrell, (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Albert W. Borrell
PO Box 391, Wilson, Kansas 67490
(Address)

Sworn to before me this 8th day of August 1974



A. E. Burns
(A. E. Burns) Notary Public.

DRILLERS LOG

No. 1 Macek

CASING RECORD:	COMPANY:	Albert Borell	DESCRIPTION:
8 5/8" @ 226.48' w/190 sx cement	CONTRACTOR:	Red Tiger Drilling Co.	NE NE NW 34-14S-10W Ellsworth County, Kansas
5 1/2" @ 2882' w/75 sx cement	COMMENCED:	July 1, 1972	
	COMPLETED:	July 14, 1972	
TOTAL DEPTH: 2886'			ELEVATION:

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>
Sand, Rock & Shale	0	228
Shale	228	468
Anhydrite	468	491
Shale	491	1405
Shale & Lime	1405	2390
Lime	2390	2535
Lime & Shale	2535	2607
Lime	2607	2886

RECEIVED
STATE CORPORATION COMMISSION
MAY 13 1974
CONSERVATION DIVISION
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

Carolyn Wolfe
Carolyn Wolfe

Subscribed and sworn to before me this 18th day of July, 1972.

Virginia H. Albert
Notary Public

