

15-053-20174-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION


Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

Ellsworth County, Sec. 31 Twp. 14 Rge. 10 (E) ~~8~~ (W)

Location as "NE/CNWSWK" or footage from lines. NE NE SE
Lease Owner Borell & Dreiling Oil, Inc.
Lease Name Borell C Well No. 1
Office Address Route, 2, Victoria, Kansas 67671
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 1-14 19 71
Application for plugging filed 1-14 19 71
Application for plugging approved 1-14 19 71
Plugging commenced 1-14 19 71
Plugging completed 1-14 19 71
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Pipe				8 5/8"	215'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

1st plug was set at 210' with 25 sacks
2nd plug was set at 40' with 10 sacks
3rd plug was set at Rat Hole with 2 sacks

RECEIVED
STATE CORPORATION COMMISSION
JAN 19 1971
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Dreiling Oil, Inc.
Address Victoria, Kansas 67671

STATE OF KANSAS, COUNTY OF ELLIS
I, Leo F. Dreiling ^{ss.} President of the Drilg. Contractor
(Contractor, Subcontractor or Contractor) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leo F. Dreiling
LEO F. DREILING, ROUTE 2, VICTORIA, KANSAS 67671
(Address)

SUBSCRIBED AND SWORN to before me this 15th day of January, 19 71

My commission expires September 19, 1974
Joseph A. Hess Notary Public.



DREILING OIL, INC.

Victoria, Kansas 67671

15-053-20174-00-00
RECEIVED
STATE CONSERVATION DIVISION
JAN 19 1971
CONSERVATION DIVISION
Wichita, Kansas

WELL LOG

Company Borell & Dreiling Oil, Inc.
 Route #2
 Victoria, Kansas 67671
 Farm Borell C No. 1
 Total Depth 3300'
 Comm. 1-9-71 Comp. 1-14-71
 Contractor Dreiling Oil, Inc.
 Victoria, Kansas 67671

Sec. 31 Twp. 14 Rng10
 Location NE NE SE
 County Ellsworth
 Elevation: 1602' K. B.
 1599' D. F.
 1597' G. R.

Casing Record

Cement Record

Production:

215' - 8 5/8"

150 sacks cement

D & A

Figures Indicate Bottom of Formations

0'	50'	Surface Soil & Sand
50'	215'	Shale
215'	307'	Shale
307'	439'	Red Bed
439'	468'	Anhydrite
468'	570'	Shale
570'	1125'	Shale
1125'	1305'	Shale & Lime Streaks
1305'	1420'	Shale with Lime Streaks
1420'	1640'	Lime & Shale
1640'	1845'	Lime & Shale
1845'	2380'	Shale & Lime
2380'	2557'	Lime
2557'	2690'	Lime & Shale
2690'	2845'	Lime & Shale
2845'	2930'	Lime
2930'	3050'	Lime with Shale Streaks
3050'	3150'	Lime & Shale
3150'	3215'	Lime & Shale
3215'	3257'	Lime
3257'	3275'	Sand
3275'	3300'	Sand & Shale & Lime
3300'	T.D.	

STATE OF KANSAS)

)ss

COUNTY OF ELLIS)

I, Leo F. Dreiling, of the Dreiling Oil, Inc., upon oath states that the above and foregoing is a true and correct copy from the Daily Drilling Report from your Borell C #1.

Leo F. Dreiling
 LEO F. DREILING

Subscribed and sworn to before me this 15th day of January, 1971.

Joseph A. Hess
 JOSEPH A. HESS NOTARY PUBLIC

My commission expires: September 19, 1974

