

15-053-20046-00-00


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Ellsworth County, Sec. 28 Twp. 14 Rge. 10 (E) W (W)
Location as "NE/CNW/SW" or footage from lines NE NW NW
Lease Owner Leo J. Dreiling Oil Company
Lease Name Vopat A Well No. 1
Office Address Route 2, Victoria, Kansas 67671
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 8-2 1968
Application for plugging filed 8-2 1968
Application for plugging approved 8-2 1968
Plugging commenced 8-2 1968
Plugging completed 8-2 1968
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Hugh Scott
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Pipe				8 5/8"	307'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

1st. plug was set @ 500' with 25 sacks cement
2nd. plug was set @ 300' with 25 sacks cement
3rd. plug was set @ 40' with 10 sacks cement
Cementing to bottom of cellar

RECEIVED
STATE CORPORATION COMMISSION
AUG 7 1968
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor L. J. Dreiling & Sons, Inc.
Address Route 2, Victoria, Kansas 67671

STATE OF KANSAS, COUNTY OF ELLIS, ss.
I, Leo F. Dreiling (employee of owner) or (~~owner~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leo F. Dreiling
LEO F. DREILING, ROUTE 2, VICTORIA, KANSAS 67671
(Address)

SUBSCRIBED AND SWORN TO before me this 5th day of August, 19 68

My commission expires September 19, 1970

Joseph A. Hess
JOSEPH A. HESS

Notary Public.

L. J. DREILING AND SONS, INC.

Victoria, Kansas 67671

15-053-20046-00-00

Company Leo J. Dreiling Oil Company WELL LOG
Route 2
Victoria, Kansas 67671

Farm Vopat A No. 1

Total Depth 2920'

Comm. 7-27-68 Comp. 8-2-68
L. J. Dreiling & Sons, Inc.
Contractor Route 2
Victoria, Kansas 67671

Casing Record
307' - 8 5/8"

Cement Record
175 sacks cement

Sec. 28 Twp. 14 Rng. 10

Location NE NW NW

County Ellsworth

Elevation: 1650' K.B.
1647' K. B.
1645' D. F.
G. R.

Production: D & A

Figures Indicate Bottom of Formations

0'	40'	Top Soil & Sand
40'	185'	Sand & Shale
185'	290'	Sand
290'	307'	Shale
307'	325'	Shale
325'	350'	Hard Sand & Iron
350'	462'	Redbed & Shale
462'	891'	Anhy.
491'	600'	Shale & Shells
600'	1141'	Shale & Shells
1141'	1280'	Shale & Lime
1280'	1470'	Shale & Shells
1470'	2140'	Lime & Shale
2140'	2227'	Shale with Lime Streaks
2227'	2460'	Shale & Lime
2460'	2920'	Lime
2920'	T.D.	


RECEIVED
STATE CORPORATION COMMISSION
AUG 7 1968
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
)ss
COUNTY OF ELLIS)

I, Leo F. Dreiling, of the L. J. Dreiling & Sons, Inc., upon oath states that the above and foregoing is a true and correct copy from the Daily Drilling Report from your Vopat A #1.

Leo F. Dreiling
LEO F. DREILING

Subscribed and sworn to before me this 5th day of August 1968.



Joseph A. Hess
JOSEPH A. HESS NOTARY PUBLIC

My Commission expires: September 19, 1970