

4-3

4-061061

W
P
R

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-051-24,214-00-00

W2 SW SW /4 SEC. 07, 14 S, 18 W
750 feet from S section line
4905 feet from E section line

Operator license# -

Lease Sentinel Hill Well # 1

Operator: State of Kansas Fee Fund

County: Ellis

Address: 2301 E. 13th Street - Dist.#4
Hays, Kansas 67601
Control #970164

Well total depth 3800 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 600 feet

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: L&M Well Service, Inc. License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: 3:00 P.M. Day: 3 Month: April Year: 1997

Plugging proposal received from: District #4 Staff

Company: Kansas Corporation Commission Phone: 913-628-1200

Were: Order 325 sxs 60/40 posmix - 10% gel and hulls.
Plug with tubing.

RECEIVED
KANSAS CORP COM
1997 APR 10 A 11:11
04-10-97

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All[], Part[X], None[]


Completed: Hour: 6:00 P.M., Day: 3, Month: April, Year: 1997

Actual plugging report: 8 5/8" to 600'w/unknown cement. 4 1/2" to 3800' w/unknown cement. RU and ran tubing to clean out bridges in casing. Cleaned to 2200' with hole open and taking water. Perforated at 2050'-1400'-700'. Ran tubing to 1970' and pumped 50 sxs cement with hulls. Pulled tubing to 1550' and pumped 75 sxs cement with hulls. Pulled tubing to 500' and circulated cement to surface with 50 sxs with hulls. Pulled tubing and tied onto annulus. Tied onto annulus and pumped 75 sxs cement with 150# hulls with cement circulating up 4 1/2" casing after 25 sxs. Tied onto 4 1/2" and pumped 50 sxs cement with 150# hulls. Pressured to 700# with casing breaking loose. S.I.

Remarks: Halliburton Cementing - Sally's Tank - L-K Wireline.

Condition of casing(in hole): GOOD BAD X Anby.plugin: YES X NO
Bottom plug(in place): YES , CALC X, NO Dakota plug: YES X, NO
Plugged through TUBING X, CASING . Elevation: 2127 GL

I did[X] / did not[] observe the plugging.


(agent)