

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-051-23, 230-50-00

NE1/4, Sec. 1, T 14 S, R 19 W1/2

990 feet from N/8 section line

1320 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5329

Lease Name Lang Well # D-2

Operator: Drilling Res. Inc.  
Name & Address: Box 278  
Victoria, Ks. 67671

County Ellis

Well Total Depth 3620 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 163

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Drilling Oil License Number \_\_\_\_\_

Address Box 278 Victoria Ks

Company to plug at: Hour: 2 PM Day: 23 Month: Nov. Year: 19 82

VERBAL PLUGGING ORDERS GIVEN TO Secretary

(company name) Dakota Top-1750-KB-Elk. 2018 (phone) 913 735-2204

were: Anhydrite 12.52-92 - Order 175 SX. cem. 50/50 per mix

6% cyl. 3% conc. Jet pits & circ. heavy mud. Pump down drill pipe,  
25 SX @ 1325, 80 SX @ 660, 40 SX @ 200, dump 1/2 SX hulls, push  
wiper plug to 40', circ. 10 SX on top, 10 SX in rat hole  
10 SX in mouse hole. No Arbuckle.

Signed Ralph Balthezore  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None None

Operations Completed: Hour: 6 PM Day: 23 Month: Nov. Year: 19 82

ACTUAL PLUGGING REPORT pumped down drill pipe.

25 SX @ 1325, 80 SX @ 660, 40 SX @ 200

dumped 1/2 SX hulls, pushed plug to 40',

circ. 10 SX on top, 10 SX rat hole. 10 SX mouse hole.

Sun cementing Co.

Remarks: \_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

I hereby certify that the above plugging instructions were given as herein stated  
and that I (did did not) observe this plugging.

RECEIVED  
STATE CORPORATION COMMISSION

DEC 7 1982

CONSERVATION DIVISION  
Wichita, Kansas

INVOICED  
DATE 12-20-82  
INV. NO. 1880-6

Signed Ralph Balthezore  
(TECHNICIAN)

FORM CP-2/3  
Rev. 9-82