

12-15

4-090503

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-109-20,544-00-00  
SE NE SW /4 SEC. 20, 14 S, 32 W  
1940 feet from S section line  
2890 feet from E section line

Operator license# 31060 Lease Krebs well # 1  
Operator: Logan Oil Company County Logan  
Address: P.O. Box 68 Well total depth 4600 feet  
Gove, Kansas 67736 Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 208 feet

149.50

Aband. oil well     , Gas well     , Input well     , SWD     , D & A X  
Plugging contractor: Emphasis Oil Operations License# 8241  
Address: Russell, Kansas 67665

Company to plug at: Hour: P.M. Day: 14 Month: December Year: 92

Plugging proposal received from: Rick Finnsey

Company: Emphasis Oil Operations Phone: -

Were: Order 200 sks. 60/40 posmix - 6% gel. and 2 sks. cello-flake.  
Spot all plugs through drill pipe with heavy mud between all plugs.

Plugging Proposal Received by: Ed Schumacher  
Plugging operations attended by agent? All[      ], Part[      ], None[ X ]

Completed: Hour: 10:00A.M., Day: 15, Month: December, Year: 92

Actual plugging report:  
1st. plug @ 2150' w/25 sks.  
2nd. plug @ 995' w/100 sks.  
3rd. plug @ 260' w/40 sks.  
4th. plug @ 40' w/10 sks.  
15 sks. in rathole.  
10 sks. in mousehole.

Remarks: By: Allied Cementing.  
Condition of casing(in hole):GOOD      BAD      Anhy.plug: YES X NO       
Bottom plug(in place): YES     , CALC     , NO X Dakota plug: YES X, NO       
Plugged through TUBING     , CASING     . Elevation: 2695 GL

I did[      ] / did not[ X ] observe the plugging. Ed Schumacher 12-23-92

DATE 1-8-93  
INV. NO. 37142

HO.

(agent) Ed Schumacher 12-23-92  
Wichita, Kansas  
Form CP-2/3

INVOICE

DEC 23 1992