

1-30

73
R

6 031484

API NUMBER 15- 109-20,496-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SE NW SE, SEC. 23, T 14 S, R 35 W7E
1650 feet from S section line
1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 30575

Lease Name Dirks Well # 23-1

Operator: Holden energy Corp
Name & Address: Suite 600 Lincoln Center
Ardmore, Ok.

County Logan 159.28
Well Total Depth 4901 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 269

Abandoned Oil Well Gas Well Input Well SWD Well O&A

Other well as hereinafter indicated

Plugging Contractor Poe Servicing License Number
Address Oberlin, Ks.

Company to plug at: Hour: PM Day: 30 Month: Jan Year: 19 91

Plugging proposal received from Rick Pickel
(company name) (phone)

were: 8 5/8 set at 269 w/175 sks cwc. 4 1/2 set at 4901 w/300 sks. TOC 3764

Perf 3957 -4802. Port collar at 2567. Order 70 sks 65/35 poz 10% gel. 200 lbs.
hulls. Plug cotton. Recover pipe. Order 300 sks 65/35 poz 10% gel 500 lbs. hulls.
B. J. Services

Feb 12 1991
02-13-91

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 4:15PM Day: 30 Month: Jan Year: 19 91

ACTUAL PLUGGING REPORT Pumped bottom plug back to 3500 w/70 sks cement blend w/

200 lbs. hulls mixed in. Maintained positive pressure. Free point at 3163. Shot off
and recovered pipe. Laid down pipe to 2550. Pumped down 4 1/2 w/115 sks cement blend
to load hole. Laid down 4 1/2 casing, tie onto 8 5/8 sq w/total of 300 sks cement
blend w/500 lbs. hulls mixed into max psi 150 lbs. Close in psi 150 lbs. Close in
psi 150 lbs. Plug complete. Elev. Anhy 1080 - 1300 Anhy 2532

Remarks: If additional description is necessary, use BACK of this form.)

INVOICED

DATE 2-22-91

INV. NO. 30812

[Signature]

Signed Carl Goodrow (TECHNICIAN)
Carl Goodrow