

Plgd. 12-11-84

6030828

API NUMBER 15-109-20, 270-00-00

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

NW SW NW SEC. 36, T 14 S, R 33 WE

3630 feet from S section line

4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5181

Lease Name SMITH Well # EE 1

Operator: DONALD C SLAWSON

County LOGAN 148.85

Name & Address 200 DOUGLAS BLDG.

Well Total Depth 4580' feet

WICHITA, KANSAS

Conductor Pipe: Size \_\_\_\_\_ feet

67202

Surface Casing: Size 8 5/8" feet 330'

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ O&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor KELSO CSG. PULLING License Number 6050

Address CHASE, KANSAS

Company to plug at: Hour: PM Day: 11 Month: 12 Year: 19 86

Plugging proposal received from BILL

(company name) KELSO CSG. (phone) \_\_\_\_\_

were: 8 5/8" SET @ 330' w/225sx. CWC. 4 1/2 SET @ 4579' w/225sx. PERF.

4183-94' ORDER 200 SX. ATN. 6 SX. HULLS ALLIED CNT. CO.

RUSSELL KANSAS WALKER WELLBROCK WATER TRUCKS. PBTD 4525'

65/35 po2. 10/60 GEL 2 1/2 DIKEI CNT. MIX. ORDER SAND & COM. CNT. 5 HOOT &

PULL PIPE.

Plugging Proposal Received by Carl Goodrow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 12: PM Day: 11 Month: 12 Year: 19 86

ACTUAL PLUGGING REPORT Dump SAND ON PBTD TO 4130' w/4 SX. COM CNT.

ON SAND w/RAILER. 165 HOTS RECOVERED 1620' of 4 1/2" CSG.

MIX. & Pump Down 8 5/8" CSG. 5 bbl slurry (10 SX.) - 6 SX. HULLS MIXED

IN w/190 SX. CNT MIX. (117 bbl slurry) LOAD HOLE & SQUEEZE

MAX. PSE 900" CLOSE IN 400" PLUG COMPLETE.

DEC 19 1986

Remarks: \_\_\_\_\_

(If additional description is necessary, use BACK of this form.)  
I (did/did not) observe this plugging.

**INVOICED**

12-19-80

DATE 1-2-87

Signed Carl Goodrow  
(TECHNICIAN)

INV. NO. 15714