

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-109-20, 275-00-00

SW, Sec 35, T 14 S, R 33 W

340 feet from N/S section line

340 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5181

Lease Name HOWARD "G" Well # 1

Operator: DONALD C SLAWSON  
Name & Address 200 DOUGLAS BLDG.  
WICHITA, KANS.  
67202

County LOGAN

Well Total Depth 4525 feet 147.06

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 331

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor SLAWSON DRUG. CO. INC. License Number \_\_\_\_\_

Address 200 DOUGLAS BLDG. WICHITA, KS. 67202

Company to plug at: Hour: 12:00 AM Day: 29 Month: JAN. Year: 1983

VERBAL PLUGGING ORDERS GIVEN TO JIM LOFTIS

(company name) SLAWSON DRUG. CO. (phone) 316-263-3201

were: 8 5/8" 331 ET SO. CUL #/225 60/40 Formix-2% GEL-3% CA-CL.

ORDER 180 50/50 Formix 6% GEL-3% CA-CL. + 8 5/8" PLUG. (BY HALLIBURTON)

SPOT WITH DRILL STEM - WITH HEAVY MUD BETWEEN ALL PLUGS

1st plug @ 2220 ET #/20 5th CNT. -> 2nd plug @ 1110 ET #/100 5th CNT.

3rd plug @ 335 ET #/40 5th CNT. -> 4th plug SOLID BRIDGE MULL'S PLUG @ 40 ET #/10 5th CNT.

10 5th IN RAT HOLE (CIRCULATE)

Signed Marion Schmidt  
(TECHNICIAN) DOIC

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None

Operations Completed: Hour: 12:15 AM Day: 29 Month: JAN. Year: 1983

ACTUAL PLUGGING REPORT ORDERED 180 50/50 Formix 6% GEL-3% CA-CL.

SPOTTED WITH DRILL STEM - WITH HEAVY MUD BETWEEN ALL PLUGS

1st plug @ 2220 ET #/20 5th CNT. -> 2nd plug @ 1110 ET #/100 5th CNT.

3rd plug @ 335 ET #/40 5th CNT. -> 4th plug SOLID BRIDGE MULL'S PLUG @ 40 ET #/10 5th CNT.

40 ET #/10 5th CNT. - 10 5th IN RAT HOLE (CIRCULATE)

CEMENTED BY HALLIBURTON CNT.

Remarks: DID NOT PENETRATE ARBUCKLE.

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 14 1983  
CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated and that I (did / did not) observe this plugging.

INVOICED

DATE JAN 28 1983

INV. NO. 3784-W

Signed Marion Schmidt  
(TECHNICIAN) DOIC

FORM CP-2/3  
Rev. 9-82