

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-109-20694-00-00
Spot: E2SE Sec/Twnshp/Rge: 26-14S-33W
1300 feet from S Section Line, 650 feet from E Section Line
Lease/Unit Name: MCGUIRE Well Number: 1
County: LOGAN Total Vertical Depth: 4460 feet

Operator License No.: 4767
Op Name: RITCHIE EXPLORATION, INC.
Address: BOX 783188 8100 E 22ND ST. N. #700
WICHITA, KS 67278

Conductor Pipe: Size feet: 8 1/44.95
Surface Casing: Size 8.625 feet: 217
Production: Size feet:
Liner: Size feet:

Well Type: DH UIC Docket No: Date/Time to Plug: 11/26/2002 7:00 PM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: ED MCKENNA Company: MURFIN DRILLING CO., INC. Phone: (316) 267-3241

Proposed Plugging Method: Order 190 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: HERB DEINES WitnessType: Plugging Operations Were Not Witnessed
Date/Time Plugging Completed: 11/26/2002 8:00 PM KCC Agent: HERB DEINES

Actual Plugging Report:

1st. Plug at 2200' w/25 sxs. Anhydrite 2189' - 2213'.
2nd. Plug at 1200' w/100 sxs.
3rd. Plug at 275' w/40 sxs.
4th. Plug at 40' w/10 sxs.
Rathole with 15 sxs.


RECEIVED
DEC 02 2002
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: PP

District: 04

Signed



(TECHNICIAN)

INVOICE

DATE 12-3-02

INV. NO. 2003060893

Form CP-2/3

NOV 27 2002