

4-061125

TO: 7
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

11-27

API Number: 15-109-20,663-00-00
140' W. of
NW NW NE /4 SEC. 25, 14 S, 33 W
4950 feet from S section line
2450 feet from E section line

Operator license# 5144

Lease: McGuire-SVGA Well # 1-25

Operator: Mull Drilling Company, Inc.

County: Logan 152.10

Address: P.O. Box 2758
Wichita, Kansas 67201

Well total depth 4680 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 219 feet

Aband. oil well, Gas well, Input well, SWD, D & A X

Plugging contractor: Abercrombie Drilling, Inc. License# 5393

Address: Wichita, Kansas 67201

Company to plug at: Hour: 1:00 P.M. Day: 27 Month: November Year: 1997

Plugging proposal received from: Tony

Company: Abercrombie Drilling Company, Inc. Phone: -

Were: Order 190 sxs 60/40 posmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received by: Herb Deines 12-03-97
Plugging operations attended by agent? All [], Part [], None [X]

Completed: Hour 3:00 P.M., Day: 27, Month: November, Year: 1997

Actual plugging report:
1st. Plug at 2150' w/25 sxs. - Anhydrite 2128' - 2150'.
2nd. Plug at 1000' w/100 sxs. - Dakota 682' - 982'.
3rd. Plug at 275' w/40 sxs. - Surface pipe 219'.
4th. Plug at 40' w/10 sxs.
Rathole with 15 sxs.

Remarks: Allied Cementing.
Condition of casing(in hole): GOOD BAD Anhy.plug: YES X NO
Bottom plug(in place): YES, CALC, NO X Dakota plug: YES X, NO
Plugged through TUBING, CASING. Elevation: 2682 GL

I did [] / did not [X] observe the plugging.

Herb Deines
BH (agent)
Form CP-2/3

INVOICED
DATE DEC 09 1997
INV. NO. 49608
11-27