

4- 070999

7-13

282R

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-109-20,538-00-00
150' East
82 82 /4 SEC. 25, 14 S, 33 W
330 feet from S section line
2490 feet from E section line

Operator license# 30798 Lease Peters well # 1

Operator: Overland Exploration Co. County Logan

Address: 200 East 1st. #505 Well total depth 4520 feet
Wichita, Kansas 67202 Conductor Pipe: 0 inch @ 0 feet
Joel A. Alberts Surface pipe 8 5/8 Inch @ 262 feet

146.90

Aband. oil well , Gas well , Input well , SWD , D & A X

Plugging contractor: Blue Goose Drilling Company License# 5104

Address: P.O. Box 1413, Great Bend, Kansas 67530

Company to plug at: Hour: A.M. Day: 13 Month: July Year: 92

Plugging proposal received from: Martin Miller

Company: Blue Goose Drilling, Inc. Phone: 316-792-5633

Were: 8 5/8" - 262' S.P. cwc. w/150 sx. 60/40 pozmix - 3% c.c. - 2% gel. by Allied Cement Company. Elev. 2824' - Anhy. - 2240'. No circulation problems. Mud condition 44 vis. - 9.8 Weight - 10 water loss. Proposal 190 sx. 60/40 pozmix - 6% gel. - 3% c.c. Spot with drill stem. Heavy mud between all plugs. 25 sx. @ 2250'. 100 sx. @ 1120'. 40 sx. @ 300'. 10 sx. @ 40'. 15 sx. in rathole (Circulate). No ar buckle.

Plugging Proposal Received by: Marion J. Schmidt

Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 10:30A.M., Day: 13, Month: July, Year: 92

Actual plugging report: Blue Goose Drilling ordered 190 sx. 60/40 pozmix 6% gel. and 1 sk. flocele. Circulated hole. Spotted and displaced cement through drill pipe. Heavy mud between all plugs.

1st. plug @ 2250' w/25 sx. cement.

2nd. plug @ 1120' w/100 sx. cement w/1 sk. flocele.

3rd. plug @ 300' w/40 sx. cement.

4th. plug @ 40' w/10 sx. cement.

15 sx. in Rathole (Circulate).

Remarks: Allied Cement Company

Condition of casing(in hole): GOOD X BAD Anhy. plug: YES X NO

Bottom plug(in place): YES X, CALC , NO Dakota plug: YES X, NO

Plugged through TUBING , CASING X. Elevation: 2824 GL

I did[] / did not[X] observe the plugging.

8-11-92

35922

Marion Schmidt
(agent)

RECEIVED
STATE CORPORATION COMMISSION

JUL 24 1992

CONSERVATION DIVISION
WICHITA, KANSAS