

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-109 - 20,312-00-00
SE, Sec. 25, T 14 S, R 33 (W) ~~N~~
330 feet from ~~N~~/S section line
1610 feet from ~~N~~/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5181

Lease Name Peters Well # F-3

Operator: Donald C. Slawson
Name & 200 Douglas Building
Address Wichita, Ks.

County Logan

Well Total Depth 4520 feet 146.90

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 345

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Slawson Drilling License Number 5657

Address 200 Douglas Building, Wichita, Ks.

Company to plug at: Hour: 11 AM Day: 4 Month: March Year: 19 84

VERBAL PLUGGING ORDERS GIVEN TO Jim Lostis

(company name) Slawson Drilling (phone) (316) 263-3201

were: Order 185 sks cement 50/50 pozmix 6% gel 3% cal. cl. 1 sk hulls 1-8 5/8 plug.
1 sk flow seal. Heavy mud between all plugs. Pump cement down drill pipe.

Elevation 2810 Anhydrite 2222-44 Arbuckle No Dakota 2000

Signed Dale F. Battagor
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 5:30 PM Day: 4 Month: March Year: 19 84

ACTUAL PLUGGING REPORT Circulated @ 2230 for 20 minutes

1st plug 25 sks @ 2230

2nd plug 100 sks @ 1110 mixed with 1 sk flow seal

3rd plug 40 sks @ 400 1 sk hulls pushed plug to 40'

4th plug 10 sks @ 40

10 sks in Rat Hole

Remarks: Lost Circulation @ 2853. Ran in 10 sks hulls regained circulation

No more trouble. Cemented by: Halliburton

RECEIVED
STATE CORPORATION COMMISSION
MAR 12 1984
03-12-84
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated
and that I (~~did~~ / did not) observe this plugging.

Signed Dale F. Battagor
(TECHNICIAN)

RECEIVED
3-14-84
0749