

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-109-20179-00-00
Spot: CNWNE Sec/Twnshp/Rge: 3-14S-33W
4620 feet from S Section Line, 1980 feet from E Section Line
Lease/Unit Name: SMOKEY VALLEY Y Well Number: 1
County: LOGAN Total Vertical Depth: 4610 feet

Operator License No.: 30742
Op Name: PALOMINO PETROLEUM, INC.
Address: 4924 SE 84TH STREET
NEWTON, KS 67114

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 301
Production: Size 4.5 feet: 3750
Liner: Size feet:

\$149.83

Well Type: OIL UIC Docket No: Date/Time to Plug: 07/24/2001 12:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MONTE ANDREWS Company: MIKE'S TESTING & SALVAGE, INC. Phone: (316) 265-4651

Proposed Plugging Method: Ordered 200 sxs 60/40 pozmix - 10% gel - 300# hulls.
Order sand and common cement.

Plugging Proposal Received By: CARL GOODROW Witness Type: Plugging Operations Were Not Witnessed
Date/Time Plugging Completed: 07/24/2001 3:00 PM KCC Agent: CARL GOODROW

Actual Plugging Report:

8 5/8" set at 301' w/225 sxs cwc. 4 1/2" set at 3750' w/150 sxs.
Prod. Perfs 3427' - 3502'.
Sanded back to 3377' with 4 sxs common cement on sand with bailer.
Shots at 2300' and 1040'. Recovered 1040' of 4 1/2".
Mixed and pumped 200 sxs cement blend with 300# hulls mixed in to 2300'.
Hole remained full.

RECEIVED
AUG - 8 2001
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

INVOICED

DATE 8-13-01

NO. 2002060215

District: 04

100.

Signed Carl Goodrow
(TECHNICIAN)

JUL 31 2001

DONALD C. SLAWSON
200 DOUGLAS BLDG.
WICHITA, KS. 67202

CONTR SLAWSON DRILLING CO. INC. CTY LOGAN

REPLACEMENT CARD:
#1 SMOKEY VALLEY "Y"

3-14-33W
C NW NE

GEOL _____ FIELD SMOKEY VALLEY EXT (± SW)

E 2875 KB 8/23/81 CARD ISSUED 1/14/82 IP P 73 BOPD & 50%
2869 GL WTR

API 15-109-20,179

WAB 3427-3455
(NEW PAY)

+	+	+
+	+	+
+	+	+

LOG	TOPS	DEPTH	DATUM
ANH		2314	+ 561
B ANH		2336	+ 539
FOR		3239	- 364
WAB		3427	- 552
HOW		3500	- 625
TOP		3550	- 675
LEC		3694	- 819
OREAD		3724	- 849
HEEB		3781	- 906
TOR		3800	- 925
LANS		3828	- 953
MUN CR		3990	-1115
STK SH		4082	-1207
B KC		4144	-1269
MARM		4184	-1309
PAW		4279	-1404

8-5/8" 301/225sx, 4 1/2" 3750/150sx
DST (1) 3430-3508 (WAB-HOW)/30-60-45-
75' REC 120' GCM, 62' VSOCM (2% o),
62' OCM (10% o), 62' VHOCM (30% o),
124' GCMO (38-54% o), 62' OCM, (14% o)
SIP 1058-1041#, FP 203-233/220-262#
FT SC 4340-1465
L CHER 4369-1494
MISS 4510-1635
PBD 3706- 831
RTD 4610-1735
LTD 4613-1738
(OVER)

CORRECTION: ELEV WAS 2675 KB

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS