

3-6

4-032299

03-20-98

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: ~~15-109-20, 223-00-00~~  
NW NE NE ~~1/4~~ SEC. 03 14 33 W  
4950 feet from S section line  
990 feet from E section line

Operator license# 30742

Lease: Smokey Valley Well # Y-2

Operator: Palomino Petroleum, Inc.

County: Logan 129.55

Address: 4924 SE 84th Street  
Newton, Kansas 67114-8827

Well total depth 3986 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 338 feet

Aband. oil well X, Gas well     , Input well     , SWD     , D & A     

Plugging contractor: D.S. & W. Well Service License# 6901

Address: Claflin, Kansas 67525

Company to plug at: Hour: A.M. Day: 6 Month: March Year: 1998

Plugging proposal received from: Kent

Company: D.S. & W. Well Service Phone:     

Were: Order 200 sxs 60/40 pozmix - 10% gel - 500# hulls - 10 sxs gel.  
Allied Cement Company.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All  , Part  , None

Completed: Hour: 10:00 A.M., Day: 6 Month: March, Year: 1998

Actual plugging report: 8 5/8" set at 338' w/225 sxs cwc. 4 1/2" set at 3985' w/175 sxs.  
D.V. at 2255' with 525 sxs cwc. Prod. Perfs 3444' - 3958'. Squeezed 4 1/2" with 40 sxs  
cement blend followed by 10 sxs gel with 500# hulls, followed by 80 sxs cement blend to Max.  
P.S.I. 1000#. Held. Squeezed 8 5/8" with 20 sxs cement blend to Max. P.S.I. 200#.  
Plug complete.

Remarks:

Condition of casing(in hole): GOOD      BAD      Anhy. plug: YES X NO       
Bottom plug(in place): YES     , CALC     , NO      Dakota plug: YES X, NO       
Plugged through TUBING     , CASING     . Elevation:      GL

I did  / did not  observe the plugging.

Carl Goodrow  
(agent)

INVOICED

DATE MAR 23 1998

INVOICE NO. 50292

15-109-20223-00-00

DONALD C. SLAWSON & NADEL & GUSSMAN  
 200 DOUGLAS BLDG. #2 SMOKY VALLEY 'Y' 3-14-33W  
 WICHITA, KS 67202 NW NE NE  
 CONTR SLAWSON DRILLING CO., INC. CTV LOGAN

GEOL RALPH RUNNE FIELD SMOKEY VALLEY EXT (1/2 W)

E 2823 KB CM 2/6/82 CARD ISSUED 4/29/82 IN D&A/KC

API 15-109-20,223

3/29/82

+	+	+
+	+	+
+	+	+

LOG	TOPS	DEPTH	DATUM
ANN	2251	+ 572	
R ANN	2272	+ 551	
FOR	3182	- 359	
WAB	3371	- 548	
HOW	3443	- 620	
TOP	3495	- 672	
LEC	3540	- 817	
HEEB	3726	- 903	
TDR	3746	- 923	
LANS	3776	- 953	
MUN CR	3938	-1115	
PSTD	3970	-1147	
LTD	3984	-1161	
RTD	3986	-1163	

8-5/8" 338/225sx, 4 1/2" 3985/175sx

- DST (1) 3338-3403(FOR, WAB, HOW)/30-60-45-75, REC 185' M W/SPTS D, SIP 1073-1043#, FP 40-90/90-140#
- DST (2) 3435-93(WAB, HOW)/30-60-45-75, 30' GIP, REC 125' OCM, 125' VSLOC, 555' MW, SIP 888-878#, FP 51-285/305-386#
- DST (3) 3632-49(LEC)/30-60-45-75, REC 125' MDY O, 50' HOCM, SIP 948-938#, FP 10-31/51-81#

INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS

(OVER)

DONALD C. SLAWSON & NADEL & GUSSMAN #2 SMOKY VALLEY "Y" 3-14-33W  
 NW NE NE

DST (4) 3734-50(HEEB, TOR)/35-60-45-75  
 REC 1426' MSW W/FEW SPTS D ON TOP,  
 SIP 1063-1053#, FP 40-442/452-682#

MICT - CO, PF (KC, MUN CR) 2/3957.5-5H, AC 250G, TSTD, NS,  
 SET BP @ 3925, PF 6/3853-66, AC 500G, SWB LD BK, TSTD, RE-  
 SET BP @ 3670, SWB DWN TO 3150', PF 4/3632-41, SWB DWN -  
 SHOW O, AC 250G, TSTD, SWB OK LD, TSTD OFF PF'S, 1.5 BPH  
 (36% O), AC 500G, TSTD, SET BP @ 3500', PF 4/3444-46, TSTD,  
 PULLEDBP @ 3420, AC 1500G, SWB DWN, REC 46 BBL'S OF LD, SWB  
 TSTD 1.17 BPH (46% O), ONFU 790' (425' W, 365' O), SWB DWN,  
 TSTD, PROD NON-COMMERCIAL, P&A

RECEIVED  
 KANSAS CORPORATION COMMISSION

JUL 23 2001

CONSERVATION DIVISION