

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 051-23837-00-00

C-NW-NE, Sec. 30, T 14 S, R 17 W/4
_____ feet from N/S section line

TECHNICIAN'S PLUGGING REPORT

_____ feet from W/E section line

Operator License # 8925

Lease Name Grabbe Well # 1

Operator: Liberty operations
Name & Address 308 w mill ^{of Completions}
Plainville KS
67663

County Ellis

Well Total Depth 3575 feet 116.19

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 7/8 feet 265

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well (D&A)

Other well as hereinafter indicated _____

Plugging Contractor Pioneer Drilg. License Number 5665

Address Plainville KS

Company to plug at: Hour: 5 AM Day: 21 Month: 4 Year: 19 84

VERBAL PLUGGING ORDERS GIVEN TO Tom Alm

(company name) Pioneer Drilg. (phone) 913-625 5783

were: order 170 5x cam. 50/50 permix 60% gel 30% cal. cl.

15x hulls 1.8 7/8 plug 15x flow seal

Heavy mud between all plugs.

Pump cam. down drill pipe.

Elev. 1947 Anhydrite-1130-73 Arbuckle 3522

Dakota 1800
147 = 450

Signed Ralph Balthazor
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ (None)

Operations Completed: Hour: 6 PM Day: 21 Month: 4 Year: 19 84

ACTUAL PLUGGING REPORT circulated @ 3520 fr. 45 mi-

25 5x @ 3520

25 5x @ 1140

100 5x @ 450 mixed w/ 15x flow seal.

15x hulls pushed plug to 40'

10 5x @ 40'

10 5x in Rat Hole.

Remarks: _____

commenting to Allied.

RECEIVED
STATE CORPORATION COMMISSION
APR 30 1984
04-30-1984
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated
and that I (did / did not) observe this plugging.

Signed Ralph Balthazor
(TECHNICIAN)

FORM CP-2/3
Rev. 9-82

INVOICED

DATE 5-1-84

INV. NO. 1318