

4-061168

10-27

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-051-24,997 -00-00
NE SW NW /4 SEC. 27, 14 S, 17 W
3630 feet from S section line
4290 feet from E section line

Operator license# 32369 Lease: Herl Well # 1-27
Operator: Delbert Gross County: Ellis 114.47
Address: d/b/a Nikki Oil Well total depth 3522 feet
1729 Agnes Dr. Conductor Pipe: 0 inch @ 0 feet
Hays, Kansas 67601 Surface pipe 8 5/8 Inch @ 221 feet

Aband. oil well , Gas well , Input well , SWD , D & A X
Plugging contractor: Discovery Drilling, Inc. License# 31548

Address: Hays, Kansas 67601
Company to plug at: Hour: 3:00 P.M. Day: 27 Month: October Year: 1998

Plugging proposal received from: Tom Alm
Company: Discovery Drilling, Inc. Phone:

Were: Order 180 sxs 60/40 posmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.
Arbuckle test recovered 5' of mud. Very tight.

Plugging Proposal Received by: Herb Deines
Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour 7:00 P.M., Day: 27, Month: October, Year: 1998

Actual plugging report:
1st. Plug at 1150' w/25 sxs. Anhydrite 1131' - 1163'.
2nd. Plug at 550' w/80 sxs. Dakota 243' - 543'.
3rd. Plug at 275' w/40 sxs. Surface pipe - 221'.
4th. Plug at 40' w/10 sxs.
Rathole with 15 sxs.
Mousehole with 10 sxs.

11-01-1998

Remarks: Allied Cementing.
Condition of casing(in hole): GOOD X BAD Anhy.plug: YES X NO
Bottom plug(in place): YES , CALC , NO X Dakota plug: YES X, NO
Plugged through TUBING , CASING . Elevation: 1968 GL

I did[] / did not[X] observe the plugging.
[Signature]
(agent)
Form CP-2/3

11-4-98
10253 10-27 JAN 29 1999