

5 020389

2-5-88

102

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 053-20,973-00-00

SW SW SW, SEC. 11, T. 14 S, R. 10 W/EX
330 feet from N/S section line
4950 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4174

Lease Name Schneider Well # 1-11

Operator: Western Oil Corporation

County Ellsworth 111.15

Name & Address P.O. Box 15277

Well Total Depth 3420 feet

Lakewood, CO 80215

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 431

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, Kansas

Company to plug at: Hour: 9:00am Day: 5 Month: 2 Year: 1988

Plugging proposal received from Darrell Kelso

(company name) Kelso Casing Pulling (phone) _____

were: Fill hole with sand to 2800' and cement with 4 sxs cement. Squeeze hole with 4 sxs hulls, 20 sxs bentonite, 1 sxs hulls, and 150 sxs 60/40 pozmix w/6% gel pumped into 8 5/8" surface casing.

Plugging Proposal Received by Gilbert J. Toman (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 9:45am Day: 5 Month: 2 Year: 1988

ACTUAL PLUGGING REPORT Hole filled with sand to 2800' and cemented with 4 sxs cement.

Hole squeezed with 4 sxs hulls, (400#), 20 sxs bentonite, 1 sxs hulls, and 150 sxs 60/40 pozmix w/6% hulls pumped into 8 5/8" surface casing.

Recovered 2000' of 5 1/2" casing. Max 800# Shut-in 200#

FEB 17 1988
CONSERVATION DIVISION
DA-17-88

Remarks: 4 1/2" of 3033 w/250 sxs PBDT 2986 Perf @2856-60, 2864-70 Allied #1869
(If additional description is necessary, use BACK of this form.)

Signed Gilbert J. Toman sep (TECHNICIAN)

INVOICED

DATE 2-22-88 WK

INV. NO. 19903