

5 020186

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-053-20, 514-00-00

C5WSW SEC. 4, T. 14 S, R. 10 (W) #

660 feet from N(S) section line

4620 feet from W(E) section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6050

Lease Name Bartunck Well # 1

Operator: Kelso Casing Pulling b/f

County Ellsworth 76.05

Name & Address Davies & Co., Inc.

Well Total Depth 2340 feet

Box 176

Conductor Pipe: Size _____ feet

Chase, Kansas 67524

Surface Casing: Size 8 5/8 feet 338

Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, Kansas 67524

Company to plug at: Hour: 9:00 AM Day: 6 Month: August Year: 1985

Plugging proposal received from Ralph Glass

(company name) Kelso Casing Pulling (phone) 316 938 2457

work: Fill hole with sand to 2135' and cement with 4 sacks

Squeeze hole with 4 sacks hulls, 15 sacks Bentonite, 25 sacks 60/40 Poz.

w/4% gel. 5 sacks Bentonite, 8 5/8" plug, 1 hulls, and 100 sacks

60/40 Poz mix w/4% gel. pump into 8 5/8" surface casing

Plugging Proposal Received by Alfred J. Loman
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 10:00 AM Day: 6 Month: August Year: 1985

ACTUAL PLUGGING REPORT Hole Filled with sand to 2135' and cemented with

4 sacks cement. Hole squeezed with 4 sacks hulls, 10 sacks

Bentonite, 25 sacks 60/40 Poz mix w/4% gel added, 5 sacks Bentonite,

1 sack hulls, 8 5/8" plug, and 100 sacks 60/40 Poz mix w/4% gel

pumped into 8 5/8" surface casing.

Max Press-800 PSIG close in Press 300 PSIG

Remarks: 4 1/2" - 2339' - 150 sacks Est. recovery 900' Filled # 40608

(If additional description is necessary, use BACK of this form.)

NOTED (If additional description is necessary, use BACK of this form.)

DATE AUG 12 1985

Signed Alfred J. Loman
(TECHNICIAN) COMMISSION

DATE _____

INV. NO. 9522

8-6