

070911

2-6

22R

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 071-20,508 - 0000

NE NW NE, SEC. 25, T 18 S, R 43 W/E  
4950 feet from S section line  
1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6033

Lease Name Schmidt "C" Well # 1-25

Operator: Murfin Drilling Company  
Name & Address: 250 N. Water, Suite 300  
Wichita, KS 67202

County Greeley (71.1)

Well Total Depth 5265 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 629

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 9:30 a.m. MST Day: 6 Month: 2 Year: 19 91

Plugging proposal received from Mike Kelso

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

were: 4 1/2" at 5264' w/200 sx cement, PBSD 5218', Perfs at 5106-36'

- 1st plug sand back to 4900' and dump 4 sx cement on top of sand through bailer,
- 2nd plug pump 50 sx cement at 2600', 3rd plug pump 80 sx cement at 1600',
- 4th plug pump 30 sx cement at 800', 5th plug pump 50 sx cement at 650',
- 6th plug pump 10 sx cement at 40'.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 5 p.m. MST Day: 6 Month: 2 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug sanded back to 4950' and dumped 4 sx cement on top of sand through bailer,

- 2nd plug pumped through 4 1/2" 10 sx gel and 50 sx cement at 2600',
- 3rd plug pumped 5 sx gel and 80 sx cement and 5 sx gel at 1600',
- 4th plug pumped 30 sx cement at 800',
- 5th plug pumped 50 sx cement at 650', 6th plug pumped 15 sx cement at 40'.

2-8-91  
FFR 8 1991

Remarks: Used 60/40 Pozmix 6% gel 1/4# floseal by Halliburton. Recovered 2800' of 4 1/2" casing. (if additional description is necessary, use BACK of this form.)

INVOICED

DATE 2-27-91

Signed Dan Johnson (TECHNICIAN)

INV. NO. 30922