

To: 1 060172 7-14  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 071-20,602-0000

NE NE NE, SEC. 36, T. 18 S, R. 43 W/EX  
330 feet from N/2 section line  
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 30689  
Operator: Marathon Oil Company  
Name & Address: P.O. Box 2690  
Cody, WY 82414

Lease Name Schmidt Well # 2-36  
County Greeley 167.70  
Well Total Depth 5160 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 556

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ O&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Cheyenne Drilling, Inc. License Number 5382

Address P.O. Box 916, Garden City, KS 67846-0916

Company to plug at: Hour: \_\_\_\_\_ Day: 14 Month: 7 Year: 19 93

Plugging proposal received from Phil Lloyd

(company name) Cheyenne Drilling, Inc. (phone) 316-277-2062

was: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2496-2600'

1st plug at 2650' with 50 sx cement, 2nd plug at 1650' with 80 sx cement,

3rd plug at 900' with 50 sx cement, 4th plug at 590' with 50 sx cement,

5th plug at 40' with 10 sx cement, 6th plug to circulate rathole with 15 sx cement,

7th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Case Morris (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 9:45 a.m. Day: 14 Month: 7 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug at 2650' with 50 sx cement,

2nd plug at 1650' with 80 sx cement, 3rd plug at 900' with 50 sx cement,

4th plug at 590' with 50 sx cement, 5th plug at 40' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement,

7th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/2# floseal by Halliburton.  
(if additional description is necessary, use BACK of this form.)

did not observe this plugging.

DATE AUG 04 1993

WV. NO. 38347

Signed \_\_\_\_\_ (TECHNICIAN)

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 19 1993  
7-19-93  
CONSERVATION DIVISION  
Wichita, Kansas