

1 051382

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200' COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-071-20,527-0000

N/2 SE NE, SEC. 26, T 18 S, R 43 W43

3660 feet from S section line

660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5952

Lease Name Settles Well # 3

Operator: Amoco Production Company

County Greeley 171.43

Name & Address P.O. Box 800, Rm. 1833

Well Total Depth 5275 feet

Denver, CO 80201

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 524

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SMD Well _____ D&A

Other well as hereinafter indicated _____

Plugging Contractor Service Drilling License Number 5987

Address 1800 4th Natl. Bank Bldg., Tulsa, OK 74119

Company to plug at: Hour: 12 a.m. Day: 22 Month: 12 Year: 19 90

Plugging proposal received from Dick Collins

(company name) Amoco (phone) 303-830-4009

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 2595' with 50 sx cement, 2nd plug at 1700' with 80 sx cement,

3rd plug at 800' with 50 sx cement, 4th plug at 554' with 40 sx cement,

5th plug at 40' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 3 a.m. Day: 22 Month: 12 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug at 2595' with 50 sx cement,

2nd plug at 1700' with 80 sx cement,

3rd plug at 800' with 50 sx cement,

4th plug at 554' with 50 sx cement,

5th plug at 40' with 10 sx cement,

6th plug to circulate rathole with 10 sx cement.

Remarks: Used 65/35 Pozmix 6% gel by Halliburton.

(If additional description is necessary, use BACK of this form.)

INVOICED (did not) observe this plugging.

DATE 1-8-91

Signed Richard W. Lacey (TECHNICIAN)

INV. NO. 30394

MAR 07 1991