

1 090043

258 R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION App.
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 071-20,489-~~000~~
NW NW NE SEC. 26, T 18 S, R 43 W/E

4950 feet from S section line
2300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5952

Lease Name Settles Well # 1

Operator: Amoco Production Company

County Greeley 172.25

Name & Address P.O. Box 800, Rm. 1833

Well Total Depth 5300 feet

Denver, CO 80201

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 500

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Cheyenne Drilling, Inc. License Number 5382

Address P.O. Box 916, Garden City, KS 67846

Company to plug at: Hour: 9:30 p.m. Day: 19 Month: 1 Year: 1990

Plugging proposal received from Randy Brewer

(company name) Amoco Production Company (phone) 303-830-4009

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at Anhydrite with 50 sx cement, 2nd plug at 1550' with 80 sx cement,

3rd plug at 530' with 50 sx cement, 4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Michael R. Wilson
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 7:30 a.m. Day: 20 Month: 1 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug at 2500' with 50 sx cement,

2nd plug at 1550' with 80 sx cement,

3rd plug at 530' with 50 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.

(If additional description is necessary, use BACK of this report.)

STATE RECEIVED
JAN 25 1990
COR. DIVISION
WICHITA, KANSAS

INVOICED

observe this plugging.

DATE JAN 26 1990

Signed Michael R. Wilson
(TECHNICIAN)

INV. NO. 27192
1-20

APR 17 1990