

To: 1050172
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 071-20,522-0000

SE NE NW NE, SEC. 26, T. 18 S, R. 43 W/E
4660 feet from S section line
1350 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License / 31593
Operator: Westport Oil & Gas Co., Inc.
Name:
Address 410 17th St., Ste. 2300
Denver, CO 80202

Lease Name Settles Well # 2
County Greeley 172.25
Well Total Depth 5300 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 508

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Allied Cementing License Number _____

Address _____

Company to plug at: Hour: 9:15 a.m. Day: 27 Month: 1 Year: 19 98

Plugging proposal received from Tony Potts

(company name) Westport Oil & Gas Co., Inc. (phone) 719 727-5020

were: 5 1/2" at 5290' w/360 sx cement, PBTD 5200', DV at 2708' w/350 sx cement, perforated at
1750' w/1200 sx, down hole perfs at 5089-5184'

1st plug pump 300 lbs. hulls, 25 sx cement, gel spacer to 2550', cement from 2550-0'.

Check backside.

Plugging Proposal Received by Kevin Strube
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:15 a.m. Day: 27 Month: 1 Year: 19 98

ACTUAL PLUGGING REPORT 1st plug pumped 300 lbs. hulls, 25 sx cement with 200 lbs. hulls
mixed in, 22 sx gel, and 230 sx cement.

Maximum pressure 1000 psi and shut in 500 psi.

Pressured up 8 5/8" X 5 1/2" annulus to 500#.

2-5-98

Remarks: Used 60/40 Pozmix 6% gel by Allied. No casing recovery.

(If additional description is necessary, use BACK of this form.)

INVOICED
I (did / ~~did not~~) observe this plugging.

DATE 2-9-98

Signed Kevin P Strube
(TECHNICIAN)

INV. NO. 50040
1-27