

3020800

3-23

164 12 R

TO:
 STATE CORPORATION COMMISSION
 CONSERVATION DIVISION - PLUGGING SECTION
 200 COLORADO DERBY BUILDING
 WICHITA, KANSAS 67202
 TECHNICIAN'S PLUGGING REPORT
 OPERATOR LICENSE # 5684
 OPERATOR: GEORGE SAGE
 NAME AND BOX 2
 ADDRESS VIRGIL, KANSAS 66870

API NUMBER 15- N/A 15-209-22574-00-08
NW, SEC. 28, T 25 S, R 15 E
2970 FEET FROM SOUTH SECTION LINE
330 FEET FROM EAST SECTION LINE
 LEASE NAME DEGREE OF HONOR WELL # 5
 COUNTY WOODSON 50.14
 WELL TOTAL DEPTH 1543 FEET
 CONDUCTOR PIPE: SIZE _____ FEET _____
 SURFACE CASING: SIZE 7 FEET 40

ABANDONED OIL WELL GAS WELL _____ INPUT WELL _____ SWD WELL _____ D/A _____
 OTHER WELL AS HEREINAFTER INDICATED _____
 PLUGGING CONTRACTOR GEORGE SAGE LICENSE NUMBER 5684
 ADDRESS BOX 2, VIRGIL, KANSAS 66870

COMPANY TO PLUG AT: HOUR: 8:00 AM DAY: 23 MONTH: 3 YEAR: 91
 PLUGGING PROPOSAL RECEIVED FROM GEORGE SAGE
 (COMPANY NAME) GEORGE SAGE (PHONE) 316-678-3440

WERE: THIS WELL CONSISTED OF 4 1/2" CASING TO 1543' THAT HAD BEEN CEMENTED IN AT TD ONLY WITH 60 SACKS OF CEMENT. THE PLUGGING PROPOSAL WAS TO PLACE A 50' CEMENT PLUG AT TD, A 50' CEMENT PLUG AT 1140', A 50' CEMENT PLUG AT 700', AND A CONTINUOUS CEMENT PLUG FROM 200' TO SURFACE. IT WAS INTENDED THAT AS MUCH 4 1/2" CASING AS POSSIBLE BE SALVAGED.

PLUGGING PROPOSAL RECEIVED BY CLAYTON TITEL
 PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL _____ PART _____ NONE

OPERATIONS COMPLETED: HOUR: 5:00 PM DAY: 23 MONTH: 3 YEAR: 91
 ACTUAL PLUGGING REPORT 5 SACKS OF CEMENT WERE PLACED AT 1543' INSIDE THE 4 1/2" CASING. 5 SACKS OF CEMENT WERE PLACED AT 1140' INSIDE THE 4 1/2" CASING. THE 4 1/2" WAS SHOT OFF AT 1010' AND PULLED TO 700'. 10 SACKS OF CEMENT WERE PUMPED THROUGH THE 4 1/2" TO 700'. THE 4 1/2" WAS PULLED TO 200'. CEMENT WAS PUMPED INTO THE 4 1/2" UNTIL CEMENT CIRCULATED FROM THE SURFACE CASING AT SURFACE. THE 200' OF 4 1/2" WAS REMOVED. 60 SACKS OF CEMENT WERE PUMPED INTO THIS WELL BY SUN CEMENTING. APPROXIMATELY 533' OF 4 1/2" CASING WERE LEFT IN THE BOTTOM OF THIS WELL.

REMARKS: _____
 (IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (XXX/DID NOT) OBSERVE THIS PLUGGING.

RECEIVED SIGNED Clayton P. Titel
 STATE CORPORATION COMMISSION (TECHNICIAN)

FORM CP-2/3

INVOICED
 DATE JUL 25 1991
 INV. NO. 32456

JUL 19 1991
 CONSERVATION DIVISION
 Wichita, Kansas