

3020798

3-23

161

92

TO:

STATE CORPORATION COMMISSION

CONSERVATION DIVISION - PLUGGING SECTION

200 COLORADO DERBY BUILDING

WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

OPERATOR LICENSE # 5684OPERATOR: GEORGE SAGENAME AND BOX 2ADDRESS VIRGIL, KANSAS 66870ABANDONED OIL WELL X GAS WELL        INPUT WELL        SWD WELL        D/A       OTHER WELL AS HEREINAFTER INDICATED       PLUGGING CONTRACTOR GEORGE SAGELICENSE NUMBER 5684ADDRESS BOX 2, VIRGIL, KANSAS 66870COMPANY TO PLUG AT: HOUR: 11:30 AM DAY: 22 MONTH: 3 YEAR: 91PLUGGING PROPOSAL RECEIVED FROM GEORGE SAGE(COMPANY NAME) GEORGE SAGE (PHONE) 316-678-3440WERE: THIS WELL CONSISTED OF 4 1/2" CASING TO 1549' THAT HAD BEEN CEMENTED IN AT TD ONLY WITH 65 SACKSOF CEMENT. THE PLUGGING PROPOSAL WAS TO PLACE A 50' CEMENT PLUG INSIDE THE 4 1/2" AT TD, PART THE 4 1/2"AT AS DEEP A DEPTH AS POSSIBLE FOR SALVAGE, PLACE A 50' CEMENT PLUG AT 700', AND PLACE A CONTINUOUSCEMENT PLUG FROM 200' TO SURFACE.PLUGGING PROPOSAL RECEIVED BY CLAYTON TITELPLUGGING OPERATIONS ATTENDED BY AGENT?: ALL        PART X NONE       OPERATIONS COMPLETED: HOUR: 5:00 PM DAY: 23 MONTH: 3 YEAR: 91ACTUAL PLUGGING REPORT 5 SACKS OF CEMENT FOLLOWED BY A RUBBER CEMENTING PLUG WERE PUMPED TO TD INSIDE THE4 1/2" CASING. THE 4 1/2" CASING WAS SHOT OFF AT 900'. THE 4 1/2" WAS PULLED TO 700' AND 10 SACKS OF CEMENTPUMPED THROUGH THE PIPE TO 700'. THE 4 1/2" WAS PULLED TO 200'. CEMENT WAS PUMPED INTO THE 4 1/2" UNTILCEMENT CIRCULATED FROM THE SURFACE CASING AT SURFACE. THE REMAINING 200' OF 4 1/2" WAS REMOVED. 55 SACKSOF CEMENT WERE PUMPED INTO THIS WELL BY SUN CEMENTING. APPROXIMATELY 649' OF 4 1/2" CASING WAS LEFT IN THEBOTTOM OF THIS WELL.REMARKS:       (IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID/XXXXXXX) OBSERVE THIS PLUGGING.

SIGNED Clayton P. Titel

(TECHNICIAN)

FORM CP-2/3

INVOICED

DATE JUL 25 1991INV. NO. 32455RECEIVED  
STATE CORPORATION COMMISSION

JUL 19 1991

CONSERVATION DIVISION  
Wichita, Kansas