

3020801

3-23

162

10  
K

TO:

STATE CORPORATION COMMISSION

CONSERVATION DIVISION - PLUGGING SECTION

200 COLORADO DERBY BUILDING

WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

OPERATOR LICENSE # 5684OPERATOR: GEORGE SAGENAME AND BOX 2ADDRESS VIRGIL, KANSAS 66870ABANDONED OIL WELL ☒ GAS WELL ☐ INPUT WELL ☐ SWD WELL ☐ D/A ☐

OTHER WELL AS HEREINAFTER INDICATED \_\_\_\_\_

PLUGGING CONTRACTOR GEORGE SAGELICENSE NUMBER 5684ADDRESS BOX 2, VIRGIL, KANSAS 66870COMPANY TO PLUG AT: HOUR: 8:00 AM DAY: 23 MONTH: 3 YEAR: 91PLUGGING PROPOSAL RECEIVED FROM GEORGE SAGE(COMPANY NAME) GEORGE SAGE (PHONE) 316-678-3440WERE: THIS WELL CONSISTED OF 4 1/2" CASING TO 1538' THAT HAD BEEN CEMENTED IN AT TD ONLY WITH 60 SACKSOF CEMENT. THE PLUGGING PROPOSAL WAS TO PLACE A 50' CEMENT PLUG AT TD INSIDE THE 4 1/2" CASING, PLACE A50' CEMENT PLUG AT 1128' INSIDE THE 4 1/2", SHOOT OFF THE 4 1/2" AT AS DEEP A DEPTH AS POSSIBLE, SALVAGEAS MUCH OF THE 4 1/2" AS POSSIBLE, PLACE A 50' CEMENT PLUG AT 700', AND PLACE A CONTINUOUS CEMENT PLUGFROM 200' TO SURFACE. PLUGGING PROPOSAL RECEIVED BY CLAYTON TITELPLUGGING OPERATIONS ATTENDED BY AGENT?: ALL ☐ PART ☐ NONE ☒OPERATIONS COMPLETED: HOUR: 5:00 PM DAY: 23 MONTH: 3 YEAR: 91ACTUAL PLUGGING REPORT 5 SACKS OF CEMENT WERE PLACED AT TD INSIDE THE 4 1/2" CASING. 5 SACKS OF CEMENTWERE PLACED AT 1128' INSIDE THE 4 1/2" CASING. THE 4 1/2" WAS SHOT OFF AT 1015' AND PULLED TO 700'. 10SACKS OF CEMENT WERE PUMPED THROUGH THE 4 1/2" TO 700'. THE 4 1/2" WAS PULLED TO 200'. CEMENT WAS PUMPEDINTO THE PIPE UNTIL CEMENT CIRCULATED FROM THE SURFACE CASING AT SURFACE. THE 200' OF 4 1/2" WAS REMOVED.60 SACKS OF CEMENT WERE PUMPED INTO THIS WELL BY SUN CEMENTING. APPROXIMATELY 523' OF 4 1/2" CASING WERELEFT IN THE BOTTOM OF THIS WELL.

REMARKS: \_\_\_\_\_

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (XXX/DID NOT) OBSERVE THIS PLUGGING.

RECEIVED  
STATE CORPORATION COMMISSIONClayton P. Titel  
(TECHNICIAN)

FORM CP-2/3

INVOICED

DATE JUL 25 1991INV. NO. 32458

JUL 19 1991

CONSERVATION DIVISION  
Wichita, Kansas