

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-113-19155-00-00
Spot: SESESE Sec/Twnshp/Rge: 30-18S-2W
612 feet from S Section Line, 660 feet from E Section Line
Lease Name: JOHNSON Well #: 1
County: MCPHERSON Total Vertical Depth: 2932 feet

Operator License No.: 5399
Op Name: AMERICAN ENERGIES CORPORATION
Address: 155 N MARKET STE 710
WICHITA, KS 67202

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: _____
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: BARRY CONSIDINE Company: _____ Phone: (620) 755-2744

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/06/2011 6:15 AM KCC Agent: SHANE JONES

Actual Plugging Report:

6/2/11 KELSO'S DROPPED SAND. 6/3/11 KELSO'S TAGGED SAND @ 2850' AND CAPPED W/4 SX. THEY CAN NOT GET HOLE LOAD FLUID DOWN AROUND 1800'. KELSO RAN TUBING TO 2100' AND COPELAND PUMPED 75 SX PLUG. TK # 36345 FOR 75 SX CLASS A. WE WAITED TILL AFTER LUNCH AND TAGGED PLUG @ 2230' AND FLUID @ 1200'. WILL LET SET OVER THE WEEKEND AND TRY TO LOAD HOLE ON MONDAY. 6/6/11 KELSO'S LOADED THE HOLE. SCHULZ OUT AND PLATED 7" TO 4 1/2". COPELAND TIED ON AND PRESSURED UP CASING TO 400 PSI. LOG TECH OF KANSAS PERFORATED @ 450'. COPELAND TIED BACK ON AND BROKE CIRCULATION WITH WATER. NO CIRCULATION BETWEEN THE 4 1/2" AND THE 7" APPEARS CEMENTED IN. WE FOUND OUT WHAT WE THOUGHT WAS SOME KIND OF HEAD THE 7" SET IN WAS ACTUALLY 8 5/8" CASING. SCHULZ BACK OUT AND PLATED 8 5/8" TO 7". COPELAND TIED BACK IN AND BROKE CIRCULATION BETWEEN 7" & 8 5/8" AND BROKE CIRCULATION BETWEEN THE 8 5/8" & 10 1/2". COPELAND SWITCHED TO CEMENT AND CIRCULATED 140 SX TO SURFACE BETWEEN THE 7" & THE 8 5/8". THEY SHUT IT IN AND PUMPED ANOTHER 60 SX TO CIRCULATE CEMENT TO SURFACE BETWEEN THE 8 5/8" AND 10 1/2". TK #36347 FOR 200 SX 60/40 POS W/4% GEL. FINISHED AT 6:15 PM. 6/7/11 I CHECKED PLUG FINDING IT DOWN 8'. OPERATOR WILL TOP OFF WHEN THE CUT OFF CASING.


Perfs:

Remarks: VERY LITTLE INFORMATION ON WELL

Plugged through: TBG

District: 02

Signed



(TECHNICIAN)

RECEIVED
JUN 27 2011

Form CP-2/3

KCC WICHITA