

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-24706-00-00
Spot: S2SWSE Sec/Twnshp/Rge: 20-17S-12W
220 feet from S Section Line, 2030 feet from E Section Line
Lease Name: RZIHA Well #: 1
County: BARTON Total Vertical Depth: 3491 feet

Operator License No.: 32639
Op Name: CORAL PRODUCTION CORPORATION
Address: 1600 STOUT ST STE 1500
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	547	0	275 sx
PROD	5.5	3490	1575	125 sx

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/06/2011 9:00 AM
Plug Co. License No.: 5893 Plug Co. Name: PRATT WELL SERVICE, INC.
Proposal Rcvd. from: JOE BORLA Company: CORAL PRODUCTION CORPORATI Phone: (308) 249-0013

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 4% gel - 500# hulls.

Plugging Proposal Received By: BRUCE RODIE Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/06/2011 3:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Set plug above perfs and topped with 4 sxs cement.
Cut casing at 1575' - pulled up 10' - pumped 125 sxs cement with 300# hulls.
Pulled casing to 810' - pumped 40 sxs cement with 100# hulls.
Pulled casing to 450' - circulated cement with 125 sxs cement with 100# hulls.
Pulled casing - topped with 5 sxs cement.

RECEIVED
KANSAS CORPORATION COMMISSION
JUN 20 2011
CONSERVATION DIVISION
WICHITA, KS

Perfs:

Top	Bot	Thru	Comments
3368	3371		LANSING J
3328	3334		LANSING H
3269	3276		LANSING F
3258	3262		LANSING E
3246	3248		LANSING D
3035	3039		PLATTSMOUTH

Remarks: QUALITY OIL WELL CEMENTING.

Plugged through: CSG

District: 04

Signed Bruce Rodie
(TECHNICIAN) CM

Form CP-2/3
7/11

JUN 17 2011