

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-179-21281-00-00  
Spot: SENENWSE Sec/Twnshp/Rge: 32-8S-29W  
2190 feet from S Section Line, 1365 feet from E Section Line  
Lease Name: THUMMEL TRUST Well #: 32-1  
County: SHERIDAN Total Vertical Depth: 4230 feet

Operator License No.: 32639  
Op Name: CORAL PRODUCTION CORPORATION  
Address: 1600 STOUT ST STE 1500  
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	266		

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/17/2011 12:00 AM  
Plug Co. License No.: 31548 Plug Co. Name: DISCOVERY DRILLING  
Proposal Revd. from: TOM ALM Company: CORAL PRODUCTION CORPORATI Phone: (303) 623-3573

Proposed Plugging Method: Ordered 220 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: NONE  
Date/Time Plugging Completed: 06/17/2011 10:30 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

1st. Plug at 2490' w/25 sxs.  
2nd. Plug at 1643' w/100 sxs.  
3rd. Plug at 315' w/40 sxs.  
4th. Plug at 40' w/10 sxs.  
Rathole with 30 sxs.  
Mousehole with 15 sxs.

Perfs:

Remarks: QUALITY OIL WELL CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed Richard Williams  
(TECHNICIAN)

CM

RECEIVED  
JUL 08 2011  
KCC WICHITA

Form CP-2/3

JUN 30 2011