

1090216

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 171-20,280 -0000

NE NE NE, SEC. 34, T 16 S, R 31 W/E  
4950 feet from ~~N~~ SE Corner of  
330 feet from ~~W~~ SE Corner of

TECHNICIAN'S PLUGGING REPORT

Operator License # 6677

Lease Name Thon Well # 1

Operator: Sandlin Oil Corporation

County Scott

Name & Address 2300 Security Life Building

Well Total Depth 4650 151.13 feet

Denver, CO 80202

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 276

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Aldebaran Drilling Co. License Number 5829

Address Box 18611, Wichita, KS 67207

Company to plug at: Hour: 10:00 pm Day: 2 Month: August Year: 1984

Plugging proposal received from Rex Lutes

(company name) Aldebaran (phone) 316-685-5372

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 2280' with 50 sx cement

2nd plug at 1500' with 50 sx cement

3rd plug at 330' with 40 sx cement  
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement, 7th plug to circulate mouse hole with 10 sx cement  
Plugging Proposal Received by R. Starluttan  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 1:00 am Day: 3 Month: August Year: 1984

ACTUAL PLUGGING REPORT 1st plug at 2280' with 50 sx cement, 2nd plug at 1500'

with 50 sx cement, 3rd plug at 330' with 40 sx cement, 4th & 5th plugs - solid bridge-

hulls - plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat

hole with 15 sx cement, 7th plug to circulate mouse hole with 10 sx cement.

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Allied No. 37494

(If additional description is necessary, use BACK of this form.)

(did/did not) observe this plugging.

RECEIVED  
STATE CORPORATION COMMISSION  
8-6-84  
AUG 06 1984

CONSERVATION DIVISION  
Wichita, Kansas

INVOICED

DATE 8-14-84

Signed R. Starluttan  
(TECHNICIAN)

INV. NO. 3075