

1 050553

R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 171-20,295-0000

NW SE NW, SEC. 28, T 16 S, R 31 W&X

3630 feet from S section line

3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5886

Lease Name Socolofsky Well # 1

Operator: Chief Drilling Co., Inc.

County Scott 151.78
(Mississippi)

Name & Address 905 Century Plaza

Well Total Depth 4670 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 341

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Warrior Drilling Co. License Number 5883

Address 905 Century Plaza, Wichita, KS 67202

Company to plug at: Hour: 8:00 pm Day: 8 Month: June Year: 19 85

Plugging proposal received from Marion Burris

(company name) Warrior (phone) 316-262-3791

where: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2883
2343-2369

1st plug at 2360' with 50 sx cement 2nd plug at 1170' with 50 sx cement

3rd plug at 660' with 50 sx cement 4th plug at 360' with 50 sx cement

5th plug solid bridge
hulls - plug at 40' -- cement to surface with 10 sx cement.

7th plug to circulate rat hole with 10 sx cement

8th plug to circulate mouse hole with 10 sx cement.

Plugging Proposal Received by Richard W. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 10:30 pm Day: 8 Month: June Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 2360' with 50 sx cement, 2nd plug at 1170' with 50
sx cement, 3rd plug at 660' with 50 sx cement, 4th plug at 360' with 50 sx cement, 5th

& 6th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement,

7th plug to circulate rat hole with 10 sx cement, 8th plug to circulate mouse hole with

10 sx cement

RECEIVED
STATE CORPORATION COMMISSION

JUN 17 1985
6-17-85
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Allied.
(If additional description is necessary, use BACK of this form)

(If not observed) observe this plugging.

Signed Richard W. Lacey
(TECHNICIAN)

DATE 6-20-85
WV. NO. 8627