

120224

3-2-89

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-171-20,379-0000
SW NW NE, SEC. 12, T 16 S, R 31 W/E
4240 feet from S section line
2260 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3988

Lease Name York "BZ" Well # 1

Operator: Slawson Exploration Company, Inc.
Name & Address 104 South Broadway
Wichita, KS 67202

County Scott 147.88

Well Total Depth 4550 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 310

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor L.D. Drilling, Inc. License Number 6039

Address Route 1, Box 183-B, Great Bend, KS 67530

Company to plug at: Hour: 5 a.m. Day: 2 Month: 3 Year: 19 89

Plugging proposal received from Greg Davidson

(company name) L.D. Drilling, Inc. (phone) 316-793-3051

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2265-88'

1st plug at 2280' with 50 sx cement, 2nd plug at 1500' with 80 sx cement,

3rd plug at 350' with 50 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 9:30 a.m. Day: 2 Month: 3 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug at 2280' with 50 sx cement,

2nd plug at 1500' with 80 sx cement,

3rd plug at 350' with 50 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Rec'd 3-14-89 JCC

Remarks: Used 60/40 Pozmix 6% gel by Allied.
(If additional description is necessary, use BACK of this form.)

I (XXXX) / did not observe this plugging.

INVOICED

Signed Duane Rankin (TECHNICIAN)

DATE 3-16-89

INV. NO. 24128