

To: 1 120494
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

11-24
API NUMBER 15- 171-20,417-0000
NE SE NW, SEC. 35, T. 16 S, R. 31 W/E
3630 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 9860
Operator: Castle Resources
Name & Address RR 1, Box 90
Hays, KS 67601

Lease Name Thon Well # 1
County Scott 148.68
Well Total Depth 4575 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 270

Abandoned Oil Well Gas Well Input Well SWD Well D&A x
Other well as hereinafter indicated

Plugging Contractor Emphasis Oil Operations License Number 8241
Address P.O. Box 506, Russell, KS 67665

Company to plug at: Hour: 11 a.m. Day: 24 Month: 11 Year: 19 90
Plugging proposal received from Tom Alm

(company name) Emphasis Oil Operations (phone) 913-483-5345

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2260-85'
1st plug at 2290' with 50 sx cement, 2nd plug at 1140' with 50 sx cement,
3rd plug at 600' with 40 sx cement, 4th plug at 300' with 50 sx cement,
5th plug at 40' with 10 sx cement, 6th plug to circulate rathole with 15 sx cement,
7th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 1:30 p.m. Day: 24 Month: 11 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug at 2290' with 50 sx cement,
2nd plug at 1140' with 50 sx cement,
3rd plug at 600' with 40 sx cement,
4th plug at 300' with 50 sx cement,
5th plug at 40' with 10 sx cement,
6th plug to circulate rathole with 15 sx cement, 7th plug to circulate mousehole with 10 sx cement.

RECORDED
STATE CORPORATION COMMISSION
12-3-90
DEC 3 1990
CONSERVATION DIVISION
WICHITA, KANSAS

Remarks: Used 60/40 Pozmix 6% gel 1/2# floseal by Halliburton.
(If additional description is necessary, use BACK of this form.)

INVOICED
(If work is done) observe this plugging.

DATE 12-7-90
W.C. NO. 30165

Signed Duane Rankin (TECHNICIAN)