

1 031129

API NUMBER 15-171-20,421-0000

To:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

S/2 NW SW, SEC. 18, T 16 S, R 33 W/R

1650 feet from S section line

4690 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6111

Lease Name Bahm Well # 1

Operator: N-B Company, Inc.

County Scott 161.75

Name &

Address Box 506

Well Total Depth 4977 feet

Russell, KS 67665

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 254

Abandoned Oil Well Gas Well Input Well SMD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Emphasis Oil Operations License Number 8241

Address P.O. Box 506, Russell, KS 67665

Company to plug at: Hour: 1 a.m. Day: 6 Month: 1 Year: 19 91

Plugging proposal received from Tom Allum

(company name) Emphasis Oil Operations (phone) 913-483-5345

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2407-27'

1st plug at 2400' with 50 sx cement, 2nd plug at 1560' with 80 sx cement,

3rd plug at 840' with 50 sx cement, 4th plug at 300' with 40 sx cement,

5th plug at 40-0' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Durrant

(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 3:45 a.m. Day: 6 Month: 1 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug at 2400' with 50 sx cement,

2nd plug at 1560' with 80 sx cement,

3rd plug at 840' with 50 sx cement,

4th plug at 300' with 40 sx cement,

5th plug at 40-0' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/4# floseal by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

FEB 13 1991

Signed Steve Durrant (TECHNICIAN)

DATE

30711