

To: 1 (913) 783-310
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 171-20,510 - 0000
SW NW NW, SEC. 27, T. 16 S, R. 32 WXX
990 feet from NX section line
330 feet from WX section line

TECHNICIAN'S PLUGGING REPORT
Operator License / 5135
Operator: John O. Farmer, Inc.
Name & Address: P.O. Box 352
Russell, KS 67665

Lease Name Wilkens "A" Well / 1
County Scott 154.37
Well Total Depth 4750 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 227

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ O&A X
Other well as hereinafter indicated _____

Plugging Contractor Discovery Drilling License Number 31548
Address P.O. Box 763, Hays, KS 67601

Company to plug at: Hour: 4 p.m. Day: 10 Month: 3 Year: 1997
Plugging proposal received from Tom Alm
(company name) Discovery Drilling (phone) 913-623-2920

Work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2400'
1st plug at 2400' with 50 sx cement, 2nd plug at 1350' with 80 sx cement,
3rd plug at 700' with 40 sx cement, 4th plug at 250' with 40 sx cement,
5th plug at 40' with 10 sx cement, 6th plug to circulate rathole with 15 sx cement,
7th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X
Operations Completed: Hour: 6:30 p.m. Day: 10 Month: 3 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug at 2400' with 50 sx cement,
2nd plug at 1350' with 80 sx cement,
3rd plug at 700' with 40 sx cement,
4th plug at 250' with 40 sx cement, 5th plug at 40' with 10 sx cement,
6th plug to circulate rathole with 15 sx cement,
7th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel w/ floseal by Allied.
(If additional description is necessary, use BACK of this form.)

Observe this plugging.

Signed [Signature] (TECHNICIAN)

DATE MAR 18 1997
INV. NO. 47766
3-10

MAINTENANCE RECEIVED
157 MAR 18 10 13 AM '97
3-18-97
PLUGGING SECTION