

To: 1 080142
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

8-29

API NUMBER 15- 171-20,517-0000

TECHNICIAN'S PLUGGING REPORT

Operator License / 5135

Operator: John O. Farmer, Inc.

Name:

Address P.O. Box 352

Russell, KS 67665

SW NE SE, SEC. 27, T 16 S, R 32 W/E

1650 feet from S section line

990 feet from E section line

Carpenter Trust

Lease Name Well / CH-2

County Scott

35.00

Well Total Depth 785 feet

Conductor Pipe: Size feet

Surface Casing: Size 5 1/2" feet 20'

Abandoned Oil Well Gas Well Input Well SWD Well D&A X Core Hole

Other well as hereinafter indicated

Plugging Contractor Allied Cementing License Number

Address

Company to plug at: Hour: 7:30 a.m. Day: 28 Month: 8 Year: 19 97

Plugging proposal received from Martin Dubois

(company name) John O. Farmer, Inc. (phone) 913-483-3144

Notes: Pipe stuck in hole at 360'

Shoot off one 20-foot drill collar at 340', pull drill pipe, cement from 340'-0', circulating cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 1 p.m. Day: 29 Month: 8 Year: 19 97

ACTUAL PLUGGING REPORT Mercury Wireline found free point at 340', shot at 340'. Left 20' 4 1/2" drill collar and 5 1/2" bit in hole. Pumped 50 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED
I (did / did not) observe this plugging.

DATE: 9-8-97

WV. NO. 48926

8-29

Signed Kevin D. Stuh
(TECHNICIAN)