

1
060442

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-171-20,289-*oof*

NE SW SW, SEC. 26, T 16 S, R 32 W/E

990 feet from S section line

4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5151

Lease Name Carpenter Well # 1-26

Operator: Gear Petroleum Co., Inc.

County Scott 154.38

Name & Address 300 Sutton Place

Well Total Depth 4750 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 349 ✓

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Warrior Drilling Company License Number 5883

Address 905 Century Plaza, Wichita, KS 67202

Company to plug at: Hour: 1:00 pm Day: 16 Month: December Year: 19 84

Plugging proposal received from Marion Burris

(company name) Warrior (phone) 316-262-3791

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 2340' with 50 sx cement

2nd plug at 1570' with 50 sx cement

3rd plug at 400' with 50 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement, 7th plug to circulate mouse hole with 10 sx cement.

Plugging Proposal Received by Paul A. Luther
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 2:15 pm Day: 16 Month: December Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 2340' with 50 sx cement, 2nd plug at 1570' with 50 sx cement, 3rd plug at 400' with 50 sx cement, 4th & 5th plugs - solid bridge - hulls -

plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with 15 sx cement, 7th plug to circulate mouse hole with 10 sx cement.

JAN 02 1985
1-2-85

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Allied.
(if additional description is necessary, use BACK of this form.)

1 (did not) observe this plugging.

Signed Paul A. Luther
(TECHNICIAN)

DATE 1-15-85
INV. NO. 6452